

6 Premier Drive, Albion Park NSW 2527 Telephone: 0242574770 Mobile No: 0418 471 343

Email: jonspin@bigpond.com.au

HAZARDOUS MATERIALS ASSESSMENT REPORT

Client: Cape Cod Australia Pty. Limited

Job details: Owner/s: Mr. D. & Mrs. M. Simpson

Location: 42 Lyton Street, Blacktown NSW

Plans for Job No: 7741/16 Revision No: C Dated: 24-03-16

Council area: BLACKTOWN CITY

Date of assessment: 19th April 2016

Our reference: HM04800416

The Client acknowledges that:

This report is provided for **the exclusive information of the Client**. It is a term and condition of the terms upon which this report is provided, that if the Client chooses to rely upon the report, that the Company and the Person making this report will not be liable to the Client or to any other Person who suffers personal or property damage or financial loss in respect of any cause of action or tort, contract or however the cause of action is said to arise.

This report is **not a guarantee or warranty** or an all-encompassing report dealing with the above property from every aspect. It is based on the condition of the property and the "**Readily Accessible Areas**" at the time of assessment. It is a reasonable attempt to identify as far as *reasonably practicable*, any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibres [SMF], **visible** at the time of assessment.

This report, based on visual assessment, will not disclose hazardous materials in inaccessible areas, not readily accessible or obstructed at the time of assessment. Areas which are not normally accessible were not assessed and include but are not limited to – inside walls, the interior of a flat roof or beneath a suspended floor filled with earth.

This report is **not a Certificate of Compliance** with the requirements of the WHS Act 2011 and WHS Regulations 2011, relevant Codes of Practice or Australian Standards or NSW Office of Environment and Heritage [OEH] Regulations.



Front eastern elevation of the residence

1. GENERAL DESCRIPTION OF THE EXISTING RESIDENCE

Estimated age:	Circa 1950 -1955	
Type of construction:	Freestanding single storey timber framed and clad with strip footings and brick piers supporting a suspended timber floor system	
External cladding:	Proprietary vinyl weatherboards over the original asbestos cement [ACM] sheet	
Roof:	Traditional cut and pitched gable ended roof structure with pre-finished corrugated profile sheet metal roofing.	

Occupancy Status: Was the residence occupied at the time of assessment?

	Yes	✓	No	Not App	licable
--	-----	---	----	---------	---------

Orientation: For the purpose of this report the front of the residence faces:

East ✓ West North South Northeast Northwest Southeast Southwest

2. AREAS ASSESSED

This assessment covers the following "Readily Accessible Areas" of the existing residence layout to identify as far as reasonably practicable any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibre insulation [SMF].

Under Floor Space ✓ Exterior	✓ Roof Surfaces	✓ Roof Cavity ✓	✓ Interior ✓	Garage	✓
------------------------------	-----------------	-----------------	--------------	--------	---

3. ASSESSMENT OF THE EXISTING RESIDENCE LAYOUT FOR HAZARDOUS MATERIALS

Area Assessed	Description and Comment	Assessment / Action
Under Floor Space	Mainly dry with areas of dampness noted. No evidence of hazardous materials was noted. Note: no work is to be undertaken in this area as part of the proposed Contract works.	No action is required.
Exterior		
Cladding	Proprietary vinyl weatherboard cladding over the original probable asbestos cement [ACM] sheet to the walls and gable ends. Note: not associated with the proposed Contract works.	All necessary steps are to be taken to protect the existing vinyl weatherboards and ACM wall cladding from damage during the course of the works.
Eave soffit lining	Proprietary vinyl weatherboard cladding over the original probable asbestos cement [ACM] sheet to the eave soffit. Note: not associated with the proposed Contract works.	All necessary steps are to be taken to protect the existing vinyl weatherboards and ACM eave soffit from damage during the course of the works.
Roofing material	Pre-finished corrugated profile sheet metal roofing. Note: approximately 60% of the roof structure to be removed to accommodate first floor addition as part of the proposed Contract works.	Remove and dispose of the sheet metal roofing in a manner approved by NSW OEH and Blacktown City Council. Appropriate dust suppression measures to be provided. No further action is required.
Front porch	Concrete deck slab Proprietary vinyl weatherboard cladding over the original probable asbestos cement [ACM] sheet to the porch soffit. Note: not associated with the proposed Contract works.	All necessary steps are to be taken to protect the existing vinyl weatherboards and ACM porch soffit from damage during the course of the works.
Rear Deck	Attached timber framed structure with a suspended timber framed deck and with a skillion roof and translucent acrylic corrugated profiled sheet roofing. Note: not associated with the proposed Contract works.	No action is required.
Painting - general	Oil based surface coating to the timber fascia. No exposed lead based paints were observed.	No action is required.

Area Assessed	Description and Comment	Assessment / Action
Interior		
Lounge room	Combination random glove plywood over the original plasterboard and plasterboard to the walls. Plasterboard ceiling lining with wide cove profiled cornice.	Appropriate dust suppression measures to be provided. No further action is required.
	Note: new square head opening to be created in <i>common</i> internal framed wall with Bedroom 2; electrical points to be relocated; and all surfaces to be made good as part of the proposed Contract works.	
Meals / Kitchen Note: roof space access in Kitchen	Combination of plasterboard and probable asbestos cement [ACM] to the walls. Combination of plasterboard ceiling with cove profile plaster cornice and probable asbestos cement [ACM] ceiling with timber cover battens [original Laundry area]. Note: not associated with the proposed Contract works.	All necessary steps are to be taken to protect the wall and ceiling lining from damage during the course of the works.
Hallway	Plasterboard to the wall linings. Plasterboard ceiling lining with cove profiled cornice. Note: existing door into Bedroom 3 to be removed and new square head opening created; and all surfaces to be made good as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.
Bedroom 1	Plasterboard to the wall linings. Plasterboard ceiling lining with wide cove profiled cornice. Note: not associated with the proposed Contract works.	No action is required.
Bedroom 2	Plasterboard to the wall linings. Plasterboard ceiling lining with wide cove profiled cornice. Note: not associated with the proposed Contract works.	No action is required.
Bedroom 3 Note: Shown as Lobby / Stairs on Construction Drawing 3 of 8 for Job No. 7741/16	Plasterboard to the wall linings. Plasterboard ceiling lining with wide cove profiled cornice. Note: new square head opening to be created in <i>common</i> internal framed wall with Lounge room; electrical points to be relocated; existing door from Hallway to be removed and new square head opening created; ceiling frame to be adjusted to accommodate internal staircase; and all surfaces to be made good as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Bathroom Note: completely stripped and renovated in 1997	Probable fibre-cement [FC] sheet under wall tiles from floor to ceiling level. Plasterboard ceiling lining with timber mould cornice. Note: not associated with the proposed Contract works.	No action is required.
Painting - general	Combination of oil based and acrylic based surface coating to ceilings, walls, doors, timber windows and trims. No exposed lead based paints were observed.	Appropriate dust suppression measures to be provided. No further action is required.
Roof Cavity	Traditional cut and pitched timber roof structure and ceiling frame. Note 1: approximately 60% of the roof structure to be removed to accommodate first floor addition as part of the proposed Contract works. Combination of synthetic mineral fibre [SMF] batt insulation and cellulose fibre [blow in] insulation overall the roof space Note 2: insulation to be retained as far as is reasonably practical as part of the proposed Contract works. Foil backed insulation to the underside of the sheet metal roofing. Minimal ceiling dust was noted.	In our opinion the air quality will not be generally affected during the course of the construction of the new first floor addition. Remove and dispose of the foil back insulation in a manner approved by NSW OEH and Blacktown City Council. Remove and dispose of the synthetic mineral fibre [SMF] batt insulation and cellulose fibre [blow in] insulation as required in a manner approved by NSW OEH and Blacktown City Council. Appropriate dust suppression measures to be provided. No further action is required.
Electrical Meter Board	Located on the southern wall. Possible asbestos cement [ACM] in backing board and lining is noted. Note: meter board and POA to be retained in current position as part of the proposed Contract works.	All necessary steps are to be taken to protect the possible ACM from damage during the course of the works.
Garage / Storage	Freestanding timber framed and clad with a pitched gable roof and corrugated profile sheet metal roofing. Probable asbestos cement [ACM] wall cladding. Note: not associated with the proposed Contract works	All necessary steps are to be taken to protect the wall cladding from damage during the course of the works.
	of materials " <i>that may"</i> contain asbestos ed as part of the proposed Contract works.	0.0m ²

DEMOLITION WORK PLAN

The partial demolition of the residence and the removal, storage, handling and disposal of building materials must be carried out as far as *reasonably practicable* in accordance with the following Regulations;

- Work Health and Safety Act 2011 and Work Health and Safety Regulations 2011
- Safe Work NSW Code of Practice How to manage and control asbestos in the workplace

- Safe Work Australia Code of Practice How to safely remove asbestos
- NSW Work Health and Safety Regulation 2011 Chapter 4 Hazardous Work
- NSW Work Health and Safety Regulation 2011 Chapter 6 Construction Work
- NSW Work Health and Safety Regulation 2011 Chapter 7 Hazardous Chemicals
- NSW Work Health and Safety Regulation 2011 Chapter 8 Asbestos
- Australian Standard AS2601 [2001] Demolition of Structures
- NSW Protection of the Environment Operations Act [1997] or as amended
- NSW Protection of the Environment Operations [Waste] Regulation [2014]
- NSW Office of Environment and Heritage [OEH] Regulations and Guidelines

A Demolition Work Plan must be submitted to BLACKTOWN CITY Council and the Principal Certifying Authority (PCA) if BLACKTOWN CITY Council is not the PCA, not less than five [5] working days **before commencing any demolition works** involving products or materials "that may" contain asbestos [ACM].

A copy of the Demolition Work Plan must be maintained on site and be made readily accessible to the Council Officer or 'workers' upon request.

ASBESTOS [ACM] REMOVAL CONTROL PLAN

<u>Safe Work Method Statement</u> - <u>Removal & Disposal of Materials that may contain Asbestos</u>

Any work involving the demolition, storage and disposal of products or materials "that may" contain asbestos [ACM] must be carried out as far as is reasonably practicable to minimise the release of airborne asbestos dust and fibres [ACD] in accordance with the following requirements;

- Relevant Work Health and Safety legislation including but not limited to; Work Health and Safety Regulation 2011 Chapter 8 Asbestos; Safe Work NSW Code of Practice How to manage and control asbestos in the workplace; Safe Work Australia Code of Practice How to safely remove asbestos and NSW Office of Environment and Heritage [OEH] requirements.
- The person with Management Control of the workplace and the licensed Asbestos Removalist must, so far as is *reasonably practicable*, and before commencing the asbestos [ACM] removal work, consult with and inform the following people about the asbestos [ACM] removal work and when the work will commence, so as to eliminate or minimise the exposure of the risks associated with asbestos:
 - The person who commissioned the asbestos removal work [Site Management]
 - A person conducting a business or undertaking at the workplace [Contractors]
 - The occupants of the domestic premises [Owner or Tenant]
 - Anyone occupying premises in the immediate vicinity of the workplace [Neighbours]
- All work procedures are to be devised as far as is reasonably practicable, to minimise the release of dust and fibres [ACD].
- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- The sign must be clearly displayed in a prominent visible position at the front of the site; containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" and including the details of the licensed Asbestos Removal Contractor [PCBU].
- When working with products and materials "that may" contain asbestos [ACM] all 'workers' are to wear personal protective equipment [PPE] including coveralls and approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715- Selection, use and maintenance of respiratory protective devices.

- As far as is reasonably practicable, use non powered hand tools for the removal of the materials that
 may contain asbestos [ACM] as these generate much less dust [ACD]. Do not use abrasive cutters
 and sanders, scrub or water blast the surface of products and materials "that may" contain asbestos
 [ACM].
- All products and materials "that may" contain asbestos [ACM] are to be kept damp to minimise as far as
 is reasonably practicable the generation of airborne asbestos dust and fibres [ACD]. Prevent and or
 contain excess run off water.
- Where it is reasonably practicable work in well ventilated areas.
- Use drop sheets to collect debris of materials that may contain asbestos [ACM]. Dispose of smaller products and materials "that may" contain asbestos [ACM] pieces and collected dust [ACD] in recommended heavy duty plastic bags which are clearly labelled "asbestos waste".
- Wet clean or use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 Industrial vacuum cleaners. Household vacuum cleaners must never be used where asbestos [ACM] or [ACD] is or may be present, even if the unit has a HEPA filter.
- Wall cladding and ceiling lining sheets "that may" contain asbestos [ACM] are not to be reused.
- All products and materials "that may" contain asbestos [ACM] or [ACD] are to be stored, transported
 and disposed of in accordance with the NSW Protection of the Environment Operations Act [1997 or as
 amended] and NSW Protection of the Environment Operations [Waste] Regulation [2014]
- All products and materials "that may" contain asbestos [ACM] or [ACD] is to be either wrapped in recommended heavy duty plastic sheeting or placed in leak proof lined bins or vehicles and appropriately covered and sealed.
- All products and materials "that may" contain asbestos [ACM] or [ACD] are to be stored in a secure area and removed from site as soon as is reasonably practicable in a covered leak proof vehicle.
- A Clearance Certificate of Statement, prepared by a suitably competent person i.e. an Occupational Hygienist, Safe Work NSW licensed Asbestos Removalist, licensed Asbestos Assessor or a "competent person" must be provided to Council upon completion of the works prior to an Occupation Certificate being issued, which confirms that the material "that may" contain asbestos [ACM] or [ACD] has been removed appropriately and the relevant Conditions of Consent have been satisfied.
- All products and materials "that may" contain asbestos [ACM] or [ACD] are to be disposed of as soon
 as is reasonably practicable, at a licensed asbestos disposal site and in a manner approved by Safe
 Work NSW, NSW Office of Environment and Heritage [OEH] or BLACKTOWN CITY Council.

Safe Work Method Statement - Removal and Disposal of Synthetic Mineral Fibre Insulation

All Contractors [PCBU's] and 'workers' involved in the removal of suspected synthetic mineral fibre [SMF] insulation are to follow the following procedures in order to minimise as far as is reasonably practicable health risks from synthetic mineral fibre [SMF] insulation. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When removing synthetic mineral fibre [SMF] insulation all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as far as is *reasonably practicable*.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of synthetic mineral fibre [SMF] insulation to prevent as far as is *reasonably practicable*, dust and fibres entering the retained living areas.

- Use approved vacuum cleaning equipment that complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust "that may" contain synthetic mineral fibres [SMF] while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of the synthetic mineral fibre [SMF] insulation in sealed approved plastic bags which are clearly labelled.
- All synthetic mineral fibre [SMF] insulation or other contaminants is to be disposed of as far as is reasonably practicable, in a manner, and at a site, approved by Safe Work NSW, NSW Office of Environment and Heritage [OEH], appropriate licensed disposal Authority or BLACKTOWN CITY Council.

Safe Work Method Statement - Removal and Disposal of Cellulose Fibre [Blow in] Insulation

All Contractors [PCBU's] and 'workers' involved in the removal of cellulose fibre [blow in] insulation are to follow the following procedures in order to minimise as far as is reasonably practicable health risks from cellulose fibre [blow in] insulation. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent entry of anyone not connected with the removal activity into the work area.
- When removing cellulose fibre [blow in] insulation all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respirator in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715- Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as much as is practical.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of cellulose fibre [blow in] insulation to prevent as far as is reasonably practicable, dust entering the retained living areas.
- Use approved vacuum cleaning equipment that complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable the release of dust that may contain lead while it is being removed. Do not use household vacuum cleaners.
- Dispose of cellulose fibre [blow in] in sealed approved plastic bags which are clearly labelled.
- All cellulose fibre [blow in] insulation or other contaminants is to be disposed of in a manner, and at a site, approved by the NSW Office of Environment and Heritage [OEH], appropriate disposal Authority or BLACKTOWN CITY Council.

Safe Work Method Statement - Lead based Paints

All Contractors [PCBU's] and 'workers' involved in the cleaning, repairing or replacement of suspected lead based paint are to follow the following procedures in order to minimise as far as is reasonably practicable, health risks from lead based paints. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When working with lead based paints all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as much as is practical.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of lead based paints to prevent as far as is reasonably practicable, dust entering the retained living areas.

- Use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust that may contain lead while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of collected lead based paint dust in sealed approved plastic bags which are clearly labelled.
- All dust containing lead or other contaminants is to be disposed of as far as reasonably practicable in a manner, and at a site, approved by Safe Work NSW, NSW Office of Environment and Heritage [OEH], appropriate disposal Authority or BLACKTOWN CITY Council.

4. AREAS NOT ASSESSED

All areas associated with the proposed building works were able to be assessed.

5. UNDETECTED HAZARDOUS MATERIALS

Due to the level of accessibility including the presence of obstructions the overall degree of risk of **undetected** hazardous materials is considered as far as *reasonably practicable* to be:

ow Moderate ✓ I	Moderate to High		High	
-----------------	------------------	--	------	--

CONFIRMATION

This document confirms that the existing residence layout described in this report has been assessed as far as *reasonably practicable* for the inclusion of hazardous materials i.e. materials "*that may*" contain asbestos [ACM] or [ACD], paints "*that may*" contain lead, ceiling dusts "*that may*" contain lead or synthetic mineral fibres [SMF] in the existing structure.

This assessment and report was carried out by: Mark Spindler

Signed for and on behalf of JONSPIN Building Services Pty. Limited

Mark Spindler Date of Issue: 20th April 2016