

6 Premier Drive, Albion Park NSW 2527
Telephone: 0242574770
Mobile No: 0418 471 343
Email: jonspin@bigpond.com.au

HAZARDOUS MATERIALS ASSESSMENT REPORT

Client: Cape Cod Australia Pty. Limited

Job details: Owner/s: Mr. A. Whitehead & Ms. A. Robson

Location: 112 West Street, Crows Nest NSW

Plans for Job No: 7710/15 Revision No: E Dated: 18-02-16

Council area: NORTH SYDNEY

Date of assessment: 2nd March 2016

Our reference: HM04680216

The Client acknowledges that:

This report is provided for **the exclusive information of the Client**. It is a term and condition of the terms upon which this report is provided, that if the Client chooses to rely upon the report, that the Company and the Person making this report will not be liable to the Client or to any other Person who suffers personal or property damage or financial loss in respect of any cause of action or tort, contract or however the cause of action is said to arise.

This report is **not a guarantee or warranty** or an all-encompassing report dealing with the above property from every aspect. It is based on the condition of the property and the "**Readily Accessible Areas**" at the time of assessment. It is a reasonable attempt to identify as far as *reasonably practicable*, any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibres [SMF], **visible** at the time of assessment.

This report, based on visual assessment, will not disclose hazardous materials in inaccessible areas, not readily accessible or obstructed at the time of assessment. Areas which are not normally accessible were not assessed and include but are not limited to – inside walls, the interior of a flat roof or beneath a suspended floor filled with earth.

This report is **not a Certificate of Compliance** with the requirements of the WHS Act 2011 and WHS Regulations 2011, relevant Codes of Practice or Australian Standards or NSW Office of Environment and Heritage [OEH] Regulations.



Front eastern elevation of the adjoining properties: No. 110 & No. 112 West Street, Crows Nest

1. GENERAL DESCRIPTION OF THE EXISTING RESIDENCE

Estimated age:	Circa 1910 -1920. Internal renovations are approximately circa 2000					
Type of construction:	Semi-detached single storey full brick / brick cavity construction on sandstone block footings with brick internal footings supporting a suspended timber floor system					
External cladding:	Clay masonry brickwork					
Roof:	Common traditional cut and pitched hipped and valley structure with front brick gable and terra cotta roofing tiles.					

Occupancy Status: Was the residence occupied at the time of assessment?

,	Yes	✓	No		Not Applicable		l
---	-----	---	----	--	----------------	--	---

Orientation: For the purpose of this report the front of the residence faces:

Е	ast	✓	West	North	South	Northeast	Northwest	Southeast	Southwest	

2. AREAS ASSESSED

This assessment covers the following "Readily Accessible Areas" of the existing residence layout to identify as far as reasonably practicable any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibre insulation [SMF].

Under Floor Space ✓ Exterior ✓ Roof Surfaces	✓ Roof Cavity	✓ Interior	✓	Carport	✓	
--	---------------	------------	---	---------	----------	--

3. ASSESSMENT OF THE EXISTING RESIDENCE LAYOUT FOR HAZARDOUS MATERIALS

Area Assessed	Description and Comment	Assessment / Action
Under Floor Space	Mainly dry sandy loam. No hazardous materials were noted. Note: no work is to be undertaken in this area as part of the proposed Contract works.	No action is required.
Exterior		
Cladding	Clay masonry brickwork Note: not affected by the proposed Contract works.	No action is required.
Eave soffit lining	Timber lining boards to top of exposed rafters. Note: not affected by the proposed Contract works.	No action is required.
Roofing material	Terra cotta tiles Note: approximately 50% of the roof structure to be removed to accommodate first floor addition as part of the proposed Contract works.	No action is required.
Front porch	Tessellated tiles to the deck. Timber lining boards to the soffit. Note: not affected by the proposed Contract works.	No action is required.
Rear deck	Suspended timber structure and decking with timber lining boards to the soffit. Note: not affected by the proposed Contract works.	No action is required.
Painting - general	Combination of oil based and acrylic based surface coating to the timber windows, timber fascia, bargeboards, eaves and trims. No exposed lead based paints were observed.	Appropriate dust suppression measures to be provided. No further action is required.
Interior		
Entry	Painted cement render walls and plasterboard to the framed wall. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: not affected by the proposed Contract works.	No action is required.

Area Assessed	Description and Comment	Assessment / Action
Hallway Note: roof attic ladder.	Painted cement render walls and with plasterboard to the framed wall. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: attic ladder and return air grill to be removed; and ceiling repaired as part of the proposed Contract works	Appropriate dust suppression measures to be provided. No further action is required.
Bedroom 1	Painted cement render walls and with plasterboard to the framed wall. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: not affected by the proposed Contract works.	No action is required.
Bedroom 2 Note: fireplace	Painted cement render walls and with plasterboard to the framed wall. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: not affected by the proposed Contract works.	No action is required.
Bedroom 3	Painted cement render walls and with plasterboard to the framed wall. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: not affected by the proposed Contract works.	No action is required.
Bathroom	Wall tiles from floor to ceiling level. Drop panel plasterboard ceiling with shadow line junction between wall and ceiling. Note: not affected by the proposed Contract works.	No action is required.
Living room Note: fireplace	Painted cement render walls. Decorative fibrous plaster ceiling with wide decorative profiled plaster cornice. Note: not affected by the proposed Contract works.	No action is required.
Kitchen	Painted cement render walls and with plasterboard to the framed wall. Plasterboard ceiling with decorative profiled plaster cornice. Note: ceiling frame to be adjusted to accommodate staircase; and all surfaces to be made good as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Dining / Family	Painted cement render walls.	No action is required.
Note: raked ceiling	Plasterboard ceiling with decorative profiled plaster cornice.	
	Note: not affected by the proposed Contract works.	
Painting - general	Combination of oil based and acrylic based surface coating to walls, doors, timber windows and trims.	Appropriate dust suppression measures to be provided. No further action is required.
	No exposed lead based paints were observed.	
Pitched Roof Cavity	Common traditional cut and pitched timber roof structure and timber ceiling frame. Note 1: approximately 50% of the roof structure to be removed to accommodate the first floor addition as part of the proposed Contract works. Synthetic mineral fibre polyester [SMF] batt insulation overall the roof space. Note 2: insulation is to be retained as part of the proposed Contract works. Note 3: framed and plasterboard clad common party / separation [fire] wall that terminates just below the roofing tiles is noted with the adjoining property, No. 110. Flexible air conditioning ductwork noted.	In our opinion the air quality will not be generally affected during the course of the construction of the new first floor addition. Appropriate dust suppression measures to be provided. No further action is required.
	Note 4: ductwork to be removed / relocated by the Owner.	
Chillian Doof	Minimum ceiling dust is noted	No action is required
Skillion Roof Cavity	Due to the method of construction no access is available.	No action is required.
	Note: not affected by the proposed Contract works.	
Electrical Meter Board	Located on the front porch <i>common privacy</i> wall.	All necessary steps are to be taken to protect the possible ACM from
	Possible asbestos cement [ACM] in backing board noted to the meter board.	damage during the course of the works.
	Note: meter board and POA to be retained in current position as part of the proposed Contract works.	
Carport	Freestanding treated pine structure with a flat roof and opaque corrugated profile acrylic sheet roofing.	No action is required.
	Note: not associated with the proposed Contract works.	
	of materials "that may" contain asbestos ved as part of the proposed Contract	0.0m ²

DEMOLITION WORK PLAN

The partial demolition of the residence and the removal, storage, handling and disposal of building materials must be carried out as far as *reasonably practicable* in accordance with the following Regulations;

- Work Health and Safety Act 2011 and Work Health and Safety Regulations 2011
- Safe Work NSW Code of Practice How to manage and control asbestos in the workplace
- Safe Work Australia Code of Practice How to safely remove asbestos
- NSW Work Health and Safety (Hazardous Substances) Regulation 2001
- NSW Work Health and Safety (Asbestos Removal Work) Regulation 2001
- Australian Standard AS2601 [2001] Demolition of Structures
- NSW Protection of the Environment Operations Act [1997]
- NSW Protection of the Environment Operations [Waste] Regulation [2005]
- NSW Office of Environment and Heritage [OEH] Regulations and Guidelines

A Demolition Work Plan must be submitted to NORTH SYDNEY Council and the Principal Certifying Authority (PCA) if NORTH SYDNEY Council is not the PCA, not less than five [5] working days **before commencing any demolition works** involving products or materials "that may" contain asbestos [ACM].

A copy of the Demolition Work Plan must be maintained on site and be made readily accessible to the Council Officer or 'workers' upon request.

Safe Work Method Statement - Removal and Disposal of Synthetic Mineral Fibre Insulation

All Contractors [PCBU's] and 'workers' involved in the removal of suspected synthetic mineral fibre [SMF] insulation are to follow the following procedures in order to minimise as far as is reasonably practicable health risks from synthetic mineral fibre [SMF] insulation. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When removing synthetic mineral fibre [SMF] insulation all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as far as is *reasonably practicable*.
- Any openings between living areas are to be sealed prior to the commencement of any removal
 work of synthetic mineral fibre [SMF] insulation to prevent as far as is reasonably practicable,
 dust and fibres entering the retained living areas.
- Use approved vacuum cleaning equipment that complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust "that may" contain synthetic mineral fibres [SMF] while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of the synthetic mineral fibre [SMF] insulation in sealed approved plastic bags which are clearly labelled.

 All synthetic mineral fibre [SMF] insulation or other contaminants is to be disposed of as far as is reasonably practicable, in a manner, and at a site, approved by Safe Work NSW, NSW Office of Environment and Heritage [OEH], appropriate licensed disposal Authority or NORTH SYDNEY Council.

Safe Work Method Statement - Lead based Paints

All Contractors [PCBU's] and 'workers' involved in the cleaning, repairing or replacement of suspected lead based paint are to follow the following procedures in order to minimise as far as is reasonably practicable, health risks from lead based paints. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When working with lead based paints all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as much as is practical.
- Any openings between living areas are to be sealed prior to the commencement of any removal
 work of lead based paints to prevent as far as is reasonably practicable, dust entering the
 retained living areas.
- Use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust
 that may contain lead while it is being removed. Do not use household vacuum cleaners even if
 the unit has a HEPA filter.
- Dispose of collected lead based paint dust in sealed approved plastic bags which are clearly labelled.
- All dust containing lead or other contaminants is to be disposed of as far as reasonably practicable in a manner, and at a site, approved by Safe Work NSW, NSW Office of Environment and Heritage [OEH], appropriate disposal Authority or NORTH SYDNEY Council.

4. AREAS NOT ASSESSED

With the exception of the skillion roof over the Family Dining room; all areas associated with the proposed building works were able to be assessed.

5. UNDETECTED HAZARDOUS MATERIALS

Due to the level of accessibility including the presence of obstructions the overall degree of risk of **undetected** hazardous materials is considered as far as *reasonably practicable* to be:

Low ✓ Moderate Moderate to High High	gh
--------------------------------------	----

CONFIRMATION

This document confirms that the existing residence layout described in this report has been assessed as far as *reasonably practicable* for the inclusion of hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], paints "that may" contain lead, ceiling dusts "that may" contain lead or synthetic mineral fibres [SMF] in the existing structure.

This assessment and report was carried out by: John Spindler

Builders Licence No. 84050C

Signed for and on behalf of JONSPIN Building Services Pty. Limited

John Spindler

Date of Issue: 2nd March 2016