
HAZARDOUS MATERIALS ASSESSMENT REPORT

Client: Cape Cod Australia Pty. Limited

Job details: Owner/s: Mr. G. Shalvi & Ms. M. Hechtman
Location: 7 Oceanview Avenue, Dover Heights

Plans for Job No: 7546/14 Revision No: D Dated: 19-06-14

Council area: WAVERLEY

Date of assessment: 20th June 2014

Our reference: HM03130614

The Client acknowledges that:

This report is provided for **the exclusive information of the Client**. It is a term and condition of the terms upon which this report is provided, that if the Client chooses to rely upon the report, that the Company and the Person making this report will not be liable to the Client or to any other Person who suffers personal or property damage or financial loss in respect of any cause of action or tort, contract or however the cause of action is said to arise.

This report is **not a guarantee or warranty** or an all-encompassing report dealing with the above property from every aspect. It is based on the condition of the property and the **"Readily Accessible Areas"** at the time of assessment. It is a reasonable attempt to identify as far as *reasonably practicable*, any significant hazardous materials i.e. materials *"that may"* contain asbestos [ACM] or [ACD], ceiling dusts *"that may"* contain lead, paints *"that may"* contain lead or synthetic mineral fibres [SMF], **visible** at the time of assessment.

This report, based on visual assessment, will not disclose hazardous materials in inaccessible areas, not readily accessible or obstructed at the time of assessment. Areas which are not normally accessible were not assessed and include but are not limited to – inside walls, the interior of a flat roof or beneath a suspended floor filled with earth.

This report is **not a Certificate of Compliance** with the requirements of the WHS Act 2011 and WHS Regulations 2011, relevant Codes of Practice or Australian Standards or NSW Office of Environment and Heritage [OEHS] Regulations.



Front northern elevation of the adjoining properties;
No. 5 & No. 7 Oceanview Avenue, Dover Heights

1. GENERAL DESCRIPTION OF THE EXISTING RESIDENCE

Estimated age:	Circa 1950
Type of construction:	Semi detached single storey full brick / brick cavity construction on a combination of sandstone block and brick footings with a suspended timber floor system
External cladding:	Clay masonry brickwork
Roof:	<i>Common</i> traditional cut and pitched hipped and valley structure with concrete roofing tiles.

Occupancy Status: Was the residence occupied at the time of assessment?

Yes	✓	No		Not Applicable	
-----	---	----	--	----------------	--

Orientation: For the purpose of this report the front of the residence faces:

East		West		North	✓	South		Northeast		Northwest		Southeast		Southwest	
------	--	------	--	-------	---	-------	--	-----------	--	-----------	--	-----------	--	-----------	--

2. AREAS ASSESSED

This assessment covers the following “*Readily Accessible Areas*” of the existing residence layout to identify as far as *reasonably practicable* any significant hazardous materials i.e. materials “*that may*” contain asbestos [ACM] or [ACD], ceiling dusts “*that may*” contain lead, paints “*that may*” contain lead or synthetic mineral fibre insulation [SMF].

Under Floor Space	✓	Exterior	✓	Roof Surfaces	✓	Roof Cavity	✓	Interior	✓	Garage	✓
-------------------	---	----------	---	---------------	---	-------------	---	----------	---	--------	---

3. ASSESSMENT OF THE EXISTING RESIDENCE LAYOUT FOR HAZARDOUS MATERIALS

Area Assessed	Description and Comment	Assessment / Action
Under Floor Space	<p>Minimum clearance noted to rear of residence.</p> <p>Mainly dry sandy loam with areas of dampness [groundwater seepage] noted in the accessible areas.</p> <p>No evidence of hazardous materials was observed.</p> <p>Note: no work is proposed into the under floor area</p>	No action is required.
Exterior		
Cladding	<p>Clay brickwork</p> <p>Note window openings to be filled in as part of the proposed Contract works</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
	<p>Possible asbestos cement [ACM] cladding with an applied texture coating finish to framed walls of rear Sunroom.</p> <p>Note: not associated with the proposed Contract works.</p>	<p>All necessary steps are to be taken to protect the cladding from damage during the course of the works.</p>
Eave lining	<p>Timber lining boards to top of exposed rafters.</p> <p>Note: existing eaves to be retained as part of the proposed Contract works</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
	<p>Possible asbestos cement to eaves of rear Sunroom.</p> <p>Note 1: fascia and gutting is displaced from rafters and current eave soffit is partially removed / displaced.</p> <p>Note 2: fascia, guttering and eave to be replaced as part of the proposed Contract works.</p>	<p>2.0m²</p> <p>Remove and dispose of the possible asbestos cement [ACM] in a manner approved by NSW OEH and Waverley Council.</p> <p>See attached Safe Work Method Statement for the removal of material <i>that may</i> contain asbestos [ACM].</p> <p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
Roofing	<p>Concrete roofing tiles to pitched roof</p> <p>Note: roof to be removed to accommodate upper floor frame as part of the proposed Contract works.</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
	<p>Pan profile sheet metal roofing to skillion roof over rear Sunroom.</p> <p>Note: roof is to be retained as part of the proposed Contract works.</p>	No action is required.

Area Assessed	Description and Comment	Assessment / Action
Garage / Patio Note: under floor access	Excavated into the site, full brick construction with a concrete floor slab and concrete slab roof forming patio deck. Note: partial balustrade to be remove to accommodate new external steps as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.
Front porch	Possible asbestos cement [ACM] soffit. Note: not part of the proposed Contract works.	All necessary steps are to be taken to protect the soffit from damage during the course of the works.
Rear deck	Hardwood decking and framed structure. Note: decking and framed structure to be retained as part of the proposed Contract works.	No action is required.
	Possible asbestos cement [ACM] infill panels between rafters to the roof. Note: pan profile metal roof sheeting to be removed to as part of the proposed Contract works.	4.8m² Remove and dispose of the possible asbestos cement [ACM] in a manner approved by NSW OEH and Waverley Council. See attached Safe Work Method Statement for the removal of material <i>that may contain asbestos</i> [ACM].
Rear retaining walls	Possible asbestos cement [ACM] cladding with an applied texture coating finish to the framed retaining walls. Note: not associated with the proposed Contract works.	All necessary steps are to be taken to protect the cladding from damage during the course of the works.
Painting - general	Combination of oil based and acrylic based surface coating to timber windows, eaves, fascia and trims. No exposed lead based paints were observed.	Appropriate dust suppression measures to be provided. No further action is required.
Interior		
Entry	Painted cement render to the walls. Gypsum plasterboard ceiling with cove profile plaster cornices. Note: not part of the proposed Contract works.	No action is required.
Sun room	Painted cement render to the walls. Gypsum plasterboard ceiling with cove profile plaster cornices. Note: wardrobe to be removed and new window installed as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Bedroom 1 Note 1: Shown as Bedroom 4 on Construction Drawing 3 of 8 for Job No. 7546/14 Note 2: skylight Note 3: air conditioning duct	Painted cement render to the walls. Gypsum plasterboard ceiling with cove profile plaster cornices. Note: skylight and ac duct to be removed; and ceiling repaired as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.
Hallway	Painted cement render to the walls. Gypsum plasterboard ceiling with cove profile plaster cornices. Note: not part of the proposed Contract works.	No action is required.
Bathroom Note 1: drop panel ceiling Note 2: roof space access	Cement render to the walls under wall tiles from floor to ceiling level. Gypsum plasterboard ceiling with square set wall/ ceiling junction. Note: not part of the proposed Contract works.	No action is required.
Bedroom 2 Note 1: Shown as Study on Construction Drawing 3 of 8 for Job No. 7546/14 Note 2: air conditioning duct	Painted cement render to the walls. Decorative panelled fibrous plaster ceiling cove profile plaster cornices. Note: ac duct to be removed; and ceiling repaired as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.
Kitchen /Dining room Note 1: Shown as Kitchen on Construction Drawing 3 of 8 for Job No. 7546/14 Note 2: skylight Note 3: air conditioning duct	Painted cement render to the walls. Gypsum plasterboard ceiling with cove profile plaster cornices. Note: skylight and ac duct to be removed; ceiling frame adjusted to accommodate internal staircase; <i>common</i> internal brick wall and bulkhead with Living room and Family room to be demolished and ceiling repaired as part of the proposed Contract works.	Appropriate dust suppression measures to be provided. No further action is required.

Area Assessed	Description and Comment	Assessment / Action
<p>Living room</p> <p>Note 1: Shown as Living/ Dining on Construction Drawing 3 of 8 for Job No. 7546/14</p> <p>Note 2: air conditioning duct</p>	<p>Painted cement render to the walls.</p> <p>Gypsum plasterboard ceiling with cove profile plaster cornices.</p> <p>Note: ac duct to be removed; <i>common</i> internal brick walls and bulkheads with Kitchen / Dining and Family room to be demolished; window in eastern external wall to be blocked up; existing rear entry door to be removed and replaced; wall surfaces and ceiling made good as part of the proposed Contract works.</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
<p>Family</p> <p>Note 1: Shown as Dining/ Living on Construction Drawing 3 of 8 for Job No. 7546/14</p> <p>Note 2: skylight</p>	<p>Painted cement render to the walls.</p> <p>Gypsum plasterboard ceiling with cove profile plaster cornices.</p> <p>Note: skylight to be removed; <i>common</i> internal brick walls and bulkheads with Kitchen / Dining and Living room to be demolished; rear <i>common</i> internal brick wall with Sunroom to be demolished; existing ceiling lining to be removed and replaced; wall surfaces and ceiling made good as part of the proposed Contract works.</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
<p>Sunroom</p>	<p>Gypsum plasterboard to framed walls.</p> <p>Gypsum plasterboard ceiling with cove profile plaster cornices.</p> <p>Note: <i>common</i> internal brick wall with Family room to be demolished; wall surfaces and ceiling made good as part of the proposed Contract works.</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
<p>Painting - general</p>	<p>Combination of oil based and acrylic based surface coating to ceilings, walls, doors, windows, reveals and trims.</p> <p>No exposed lead based paints were observed.</p>	<p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>

Area Assessed	Description and Comment	Assessment / Action
Pitched Roof Cavity	<p>Traditional cut and pitched timber roof structure and ceiling frame.</p> <p>Note 1: roof structure to be removed to accommodate upper floor addition as part of the proposed Contract works.</p> <p>Synthetic mineral fibre [polyester] batt insulation overall the roof space.</p> <p>Note 2: insulation to be retained as part of the proposed Contract works.</p> <p>Sarking is provided to the underside of the concrete roofing tiles.</p> <p>Minimal ceiling dust was noted.</p> <p>Note 3: <i>common</i> brick party wall with adjoining property, No. 5 is noted.</p>	<p>In our opinion the air quality will not be generally affected during the course of the construction of the new upper floor frame.</p> <p>Appropriate dust suppression measures to be provided.</p> <p>No further action is required.</p>
Skillion Roof Cavity	<p>Inspection of the roof cavity over the rear Sunroom was not carried out due to the method of construction.</p> <p>Note: not part of the proposed Contract works.</p>	No action is required.
Electrical Meter Board	<p>Located on the eastern wall adjacent to front entry.</p> <p>In our opinion the existing meter board complies with current industry and Supply Authority requirements.</p> <p>Note: to be retained in current position as part of the proposed Contract works.</p>	No action is required.
Approximate area of materials “<i>that may</i>” contain asbestos [ACM] to be removed as part of the proposed Contract works.		6.8m²

DEMOLITION WORK PLAN

The partial demolition of the residence and the removal, storage, handling and disposal of building materials must be carried out as far as *reasonably practicable* in accordance with the following Regulations;

- Work Health and Safety Act 2011 and Work Health and Safety Regulations 2011
- WorkCover NSW - Code of Practice - *How to manage and control asbestos in the workplace*
- Safe Work Australia - Code of Practice - *How to safely remove asbestos*
- NSW Work Health and Safety (Hazardous Substances) Regulation 2001
- NSW Work Health and Safety (Asbestos Removal Work) Regulation 2001
- Australian Standard AS2601 [2001] - Demolition of Structures
- NSW Protection of the Environment Operations Act [1997]
- NSW Protection of the Environment Operations [Waste] Regulation [2005]

- NSW Office of Environment and Heritage [OEH] Regulations and Guidelines

A Demolition Work Plan must be submitted to WAVERLEY Council and the Principal Certifying Authority (PCA) if WAVERLEY Council is not the PCA, not less than five [5] working days **before commencing any demolition works** involving products or materials “*that may*” contain asbestos [ACM].

A copy of the Demolition Work Plan must be maintained on site and be made readily accessible to the Council Officer or ‘workers’ upon request.

ASBESTOS REMOVAL CONTROL PLAN

Safe Work Method Statement - Removal & Disposal of Materials *that may* contain Asbestos

Any work involving the demolition, storage and disposal of products or materials “*that may*” contain asbestos [ACM] must be carried out as far as *reasonably practicable* to minimise the release of airborne asbestos dust and fibres [ACD] in accordance with the following requirements;

- Relevant Work Health and Safety legislation including but not limited to WorkCover NSW - Code of Practice - *How to manage and control asbestos in the workplace*; Safe Work Australia - Code of Practice - *How to safely remove asbestos* and NSW Office of Environment and Heritage [OEH] requirements.
- The person with Management Control of the workplace and the licensed Asbestos Removalist must, so far as *reasonably practicable*, and before commencing the asbestos [ACM] removal work, consult with and inform the following people about the asbestos [ACM] removal work and when the work will commence, so as to eliminate or minimise the exposure of the risks associated with asbestos:
 - The person who commissioned the asbestos removal work [Site Management]
 - A person conducting a business or undertaking at the workplace [Contractors]
 - The occupants of the domestic premises [Owner or Tenant]
 - Anyone occupying premises in the immediate vicinity of the workplace [Neighbours]
- All work procedures are to be devised as far as *reasonably practicable* to minimise the release of dust and fibres [ACD].
- Appropriate warning signage and barricades are to be erected to prevent as far as *reasonably practicable*, entry of anyone not connected with the removal activity into the work area.
- The sign must be clearly displayed in a prominent visible position at the front of the site; containing the words “**DANGER ASBESTOS REMOVAL IN PROGRESS**” and including the details of the licensed Asbestos Removal Contractor [PCBU].
- When working with products and materials “*that may*” contain asbestos [ACM] all ‘workers’ are to wear personal protective equipment [PPE] including coveralls and approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 – *Respiratory Protection devices* and AS/NZS1715- *Selection, use and maintenance of respiratory protective devices*.
- As far as *reasonably practicable*, use non powered hand tools for the removal of the materials *that may* contain asbestos [ACM] as these generate much less dust [ACD]. **Do not use** abrasive cutters and sanders, scrub or water blast the surface of products and materials “*that may*” contain asbestos [ACM].

- All products and materials “*that may*” contain asbestos [ACM] are to be kept damp to minimise as far as *reasonably practicable* the generation of airborne asbestos dust and fibres [ACD]. Prevent and or contain excess run off water.
- Where *reasonably practicable* work in well ventilated areas.
- Use drop sheets to collect debris of materials *that may* contain asbestos [ACM]. Dispose of smaller products and materials “*that may*” contain asbestos [ACM] pieces and collected dust [ACD] in recommended heavy duty plastic bags which are clearly labelled “**asbestos waste**”.
- Wet clean or use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 – *Industrial vacuum cleaners*. Household vacuum cleaners **must never be used** where asbestos [ACM] or [ACD] is or may be present, even if the unit has a HEPA filter.
- Wall cladding and ceiling lining sheets “*that may*” contain asbestos [ACM] are **not** to be reused.
- All products and materials “*that may*” contain asbestos [ACM] or [ACD] are to be stored, transported and disposed of in accordance with the NSW Protection of the Environment Operations Act [1997] and NSW Protection of the Environment Operations [Waste] Regulation [2005]
- All products and materials “*that may*” contain asbestos [ACM] or [ACD] is to be either wrapped in recommended heavy duty plastic sheeting or placed in leak proof lined bins or vehicles and appropriately covered and sealed.
- All products and materials “*that may*” contain asbestos [ACM] or [ACD] are to be stored in a secure area and removed from site as soon as *reasonably practicable* in a covered leak proof vehicle.
- A Clearance Certificate of Statement, prepared by a suitably *competent person* i.e. an Occupational Hygienist, WorkCover NSW licensed Asbestos Removalist, licensed Asbestos Assessor or a “*competent person*” must be provided to Council upon completion of the works prior to an Occupation Certificate being issued, which confirms that the material “*that may*” contain asbestos [ACM] or [ACD] has been removed appropriately and the relevant Conditions of Consent have been satisfied.
- All products and materials “*that may*” contain asbestos [ACM] or [ACD] are to be disposed of as soon as *reasonably practicable*, at a licensed asbestos disposal site and in a manner approved by WorkCover NSW, NSW Office of Environment and Heritage [OEH] or WAVERLEY Council.

Safe Work Method Statement – Lead based Paints

All Contractors [PCBU's] and ‘workers’ involved in the cleaning, repairing or replacement of suspected lead based paint are to follow the following procedures in order to minimise as far as *reasonably practicable*, health risks from lead based paints. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as *reasonably practicable*, entry of anyone not connected with the removal activity into the work area.
- When working with lead based paints all ‘workers’ are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 - *Respiratory Protection devices* and AS/NZS1715 - *Selection, use and maintenance of respiratory protective devices*. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.

- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as much as is practical.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of lead based paints to prevent as far as *reasonably practicable*, dust entering the retained living areas.
- Use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 - *Industrial vacuum cleaners*, to prevent the release of dust that may contain lead while it is being removed. **Do not use** household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of collected lead based paint dust in sealed approved plastic bags which are clearly labelled.
- All dust containing lead or other contaminants is to be disposed of as far as *reasonably practicable* in a manner, and at a site, approved by WorkCover NSW, NSW Office of Environment and Heritage [OEH], appropriate disposal Authority or WAVERLEY Council.

4. AREAS NOT ASSESSED

All areas associated with the proposed building works were able to be assessed.

5. UNDETECTED HAZARDOUS MATERIALS

Due to the level of accessibility including the presence of obstructions the overall degree of risk of **undetected** hazardous materials is considered as far as *reasonably practicable* to be:

Low	✓	Moderate		Moderate to High		High	
-----	---	----------	--	------------------	--	------	--

CERTIFICATION

This document certifies that the existing residence layout described in this report has been assessed as far as *reasonably practicable* for the inclusion of hazardous materials i.e. materials “that may” contain asbestos [ACM] or [ACD], paints “that may” contain lead, ceiling dusts “that may” contain lead or synthetic mineral fibres [SMF] in the existing structure.

This assessment and report was carried out by: John Spindler

Builders Licence No. 84050C

Signed for and on behalf of JONSPIN Building Services Pty. Limited



John Spindler

Date of Issue: 30th June 2014

