

Legend

ABL	Alarm Box
TBC	Telstra Box
DP	Downpipe
EL	Eave Light
EF	Exhaust Fan
GPO	Power Outlet
HWU	Hot Water Unit Wall Mounted
MH	Manhole
MB	Meter Box - Electrical
GAS	Meter - Gas
WATER	Meter - Water
SL	Skylight
	Smoke Detector - Existing
ST	Solar Tube
WL	Wall Light
T	Tap - Garden
VP	Sewer Vent Pipe
	Smoke Detector - New

**PROTECT PROBABLE AC (ACM)
IN GABLE END CLADDING FROM
DAMAGE DURING THE COURSE
OF THE WORKS**



A

A

DEMOLITION & DISPOSAL SUMMARY

PARTIAL DEMOLITION OF THE RESIDENCE & THE REMOVAL, STORAGE, HANDLING & DISPOSAL OF BUILDING MATERIALS MUST BE CARRIED OUT "AS FAR AS IS REASONABLY PRACTICABLE" & IN ACCORDANCE WITH THE FOLLOWING WORK PLACE REGULATIONS;

- WORK HEALTH & SAFETY ACT 2011 & REGULATIONS 2011
- SAFE WORK NSW GUIDELINES & CODES OF PRACTICE
- SAFEWORK AUSTRALIA GUIDELINES & CODES OF PRACTICE
- AUSTRALIAN STANDARD AS2601 (2001) - DEMOLITION OF STRUCTURES
- NSW PROTECTION OF THE ENVIRONMENT OPERATIONS ACT -1997 [or as amended]
- NSW PROTECTION OF THE ENVIRONMENT OPERATIONS [WASTE] REGULATION - 2014
- RELEVANT NSW OFFICE OF ENVIRONMENT & HERITAGE [OE] GUIDELINES
- WAVERLEY COUNCIL CONDITIONS FOR DEVELOPMENT CONSENT



HAZARDOUS MATERIALS SUMMARY

DEMOLITION & DISPOSAL OF PRODUCTS & MATERIAL "THAT MAY" CONTAIN ASBESTOS (ACM) OR (ACD) IS TO BE "AS FAR AS IS REASONABLY PRACTICABLE" & IN ACCORDANCE WITH SAFE WORK NSW & SAFE WORK AUSTRALIA - CODES OF PRACTICE FOR THE SAFE REMOVAL OF ASBESTOS & ALL OTHER AUTHORITY REQUIREMENTS.

PROBABLE AC (ACM) SHEET TO FRONT GABLE CLADDING

MINIMUM CEILING DUST OBSERVED WITHIN THE ROOF SPACE

NIL EXPOSED LEAD BASED PAINTS OBSERVED

Ground Floor Plan