

6 Premier Drive, Albion Park NSW 2527
Telephone: 0242574770
Mobile No: 0418 471 343
Email: jonspin@bigpond.com.au

HAZARDOUS MATERIALS ASSESSMENT REPORT

Client: Cape Cod Australia Pty. Limited

Job details: Owner: Mr & Mrs Robertson

Location: 2A Bayview St Concord

Plans for Job No: 7674/15 Revision No: D Dated: 30-9-15

Council area: Canada Bay

Date of assessment: 9 October 2015

Our reference: HM04311015

The Client acknowledges that:

This report is provided for **the exclusive information of the Client**. It is a term and condition of the terms upon which this report is provided, that if the Client chooses to rely upon the report, that the Company and the Person making this report will not be liable to the Client or to any other Person who suffers personal or property damage or financial loss in respect of any cause of action or tort, contract or however the cause of action is said to arise.

This report is **not a guarantee or warranty** or an all-encompassing report dealing with the above property from every aspect. It is based on the condition of the property and the "**Readily Accessible Areas**" at the time of assessment. It is a reasonable attempt to identify as far as *reasonably practicable*, any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibres [SMF], **visible** at the time of assessment.

This report, based on visual assessment, will not disclose hazardous materials in inaccessible areas, not readily accessible or obstructed at the time of assessment. Areas which are not normally accessible were not assessed and include but are not limited to – inside walls, the interior of a flat roof or beneath a suspended floor filled with earth.

This report is **not a Certificate of Compliance** with the requirements of the WHS Act 2011 and WHS Regulations 2011, relevant Codes of Practice or Australian Standards or NSW Office of Environment and Heritage [OEH] Regulations.



Front elevation of the dwelling

1. GENERAL DESCRIPTION OF THE EXISTING RESIDENCE

Estimated age:	Circa 1950		
Type of construction: Single storey cavity brick construction			
External cladding: Face brickwork and FC sheeting			
Roof:	Concealed butterfly		

Occupancy Status: Was the residence occupied at the time of assessment?

Yes ✓ No Not Applicab	le
-----------------------	----

Orientation: For the purpose of this report the front of the residence faces:

2. AREAS ASSESSED

This assessment covers the following "Readily Accessible Areas" of the existing residence layout to identify as far as reasonably practicable any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibre insulation [SMF].

ler Floor Space	Exterior <	Roof Surfaces	✓	Roof Cavity	✓	Interior	✓	Garage	✓	
-----------------	------------	---------------	---	-------------	---	----------	---	--------	---	--

ASSESSMENT OF THE EXISTING RESIDENCE LAYOUT FOR HAZARDOUS MATERIALS

Area Assessed	Description and Comment	Assessment / Action		
Under Floor Space	Not accessed	No work planned to under floor space No action required		
Exterior		The detion requires		
Face brickwork	Note 1: Part parapet walls to be demolished	Appropriate dust suppression measures to be provided No further action required		
Patio soffit	Reinforced concrete	No work planned to this area No action required		
Roofing	Asbestos cement [super 6] to be removed to existing roof excluding rear skillion roof Note 1: Protect roof sheeting to rear skillion during course for works	Remove and dispose of the possible asbestos cement flat sheet [ACM] in a manner approved by NSW OEH and Local Council Note: See attached Safe Work Method Statement for the removal of material that may contain asbestos [ACM]. Appropriate dust suppression measures to be provided		
Painting - general	Combination of oil based enamel and acrylic to eave soffits and trims No lead based paints were observed	Appropriate dust suppression measures to be provided No further action required		
Interior				
Kitchen	Rendered & painted brickwork Fibrous plaster ceiling with ornate cornice	No work planned for this area No further action required		
Dining	Rendered & painted brickwork Fibrous plaster ceiling with ornate cornice Note 1: Brick wall between bed room 2 to be partially demolished	Appropriate dust suppression measures to be provided		

Area Assessed	Description and Comment	Assessment / Action		
		No further action required		
Living room	Rendered & painted brickwork Fibrous plaster ceiling with ornate cornice	No work planned for this area No further action required		
Bedroom 1 Note: Shown as Bedroom 4 on Construction Drawing 3 of 8 No. 7674/15	Rendered & painted brickwork Fibrous plaster ceiling with ornate cornice	No work planned for this area No further action required		
Bedroom 2 Note: Shown as Stair room on Construction Drawing 3 of 8 No. 7674/15	Rendered & painted brickwork Fibrous plaster ceiling with ornate cornice Note 1: Brick wall between dining to be partially demolished	Appropriate dust suppression measures to be provided No further action required		
Bathroom	Ceramic tiles 1.6m high to walls over brickwork Painted plasterboard to ceiling with cove cornice	No work proposed for this area No further action required		
Hall	Rendered & painted brickwork Painted plasterboard to ceiling with cove cornice	No work planned for this area No further action required		
Laundry	Rendered and painted brickwork walls with Painted plasterboard to ceiling with cove cornice	Protect from damage during course of works No further action required		
WC	Rendered and painted brickwork walls with Painted plasterboard to ceiling with cove cornice	Protect from damage during course of works No further action required		
Family room	Rendered and painted brickwork walls and plasterboard over timber frame Painted plasterboard to ceiling with cove cornice	Protect from damage during course of works No further action required		
General				
Painting - general	Acrylic / plastic paint to ceilings, walls. Enamel paint to doors and trims.	Appropriate dust suppression measures to be provided. No further action is		

Area Assessed	Description and Comment	Assessment / Action		
	No lead based paints were observed	required		
Roof Cavity	Synthetic mineral fibre batt insulation Pitched timber roof structure Note: 1. Minimal ceiling dust was noted Note: 2. Sarking is not installed under the roof sheets	In our opinion the air quality will not be affected during the course of the construction of the new upper floor frame Appropriate dust suppression measures to be provided		
Skillion roof cavity	No access possible to skillion roof over Laundry and family room	Appropriate dust suppression measures to be provided No work planned for this area		
Electrical Meter Board	Located at front LH corner dwelling To be retained in present location.	No work proposed to this area No further action is required		
Approximate area of n to be removed as part	89.9m ²			

4. AREAS ASSESSED

All areas assessed where access was available and where required

5. UNDETECTED HAZARDOUS MATERIALS

Due to the level of accessibility including the presence of obstructions the overall degree of risk of **undetected** hazardous materials is considered as far as *reasonably practicable* to be:

Low ✓ Moderate Moderate to High High	
--------------------------------------	--

CERTIFICATION

This document certifies that the existing residence layout described in this report has been assessed as far as *reasonably practicable* for the inclusion of hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], paints "that may" contain lead, ceiling dusts "that may" contain lead or synthetic mineral fibres [SMF] in the existing structure.

This assessment and report was carried out by: Garry Pearce

Builders Licence No. 147214C

Signed for and on behalf of JONSPIN Building Services Pty. Limited

Garry Pearce

Date of Issue: 12 October 2014

A1. Use of Asbestos

Only fibro products made before 1987 contain asbestos in NSW, for example the use of asbestos was discontinued in fibro sheets by 1982, in corrugated sheets by 1984 and in other products by 1986. The manufacture and use of asbestos product was banned nationally from 31st December 2003.

A2. What Are The Risks?

"Breathing in asbestos fibre can cause asbestosis, lung cancer and mesothelioma. This does not automatically mean that your health is at risk if you find your home is made from or contains asbestos cement [fibro] products. Studies have shown that these products, if in sound condition and left undisturbed are not a significant health risk. If the asbestos cement fibres remain firmly bound to a solid cement sheet or structure, generally you do not need to remove the asbestos cement [fibro] or even coat it.

Health problems usually occur when people are unaware of the hazards of working with asbestos cement [fibro]. The important point is to use commonsense and follow safety guidelines working with asbestos cement [fibro] products should not be a problem". [Extract from - Fibro & Asbestos – A Renovator and Homeowners Guide – WorkCover NSW 2004]

<u>Safe Work Method Statement – Non friable In-situ Asbestos Cement Sheeting</u>

All work procedures are to be devised as far as *reasonably practicable* to minimise the release of dust and fibres [ACD]. A checklist of safety precautions when working with asbestos cement products [ACM] should include but is not limited to the following:

- Appropriate warning signage and barricades are to be erected to prevent entry of anyone not connected with the removal activity into the work area.
 - The sign must be clearly displayed in a prominent visible position at the front of the site; containing the words "**DANGER ASBESTOS REMOVAL IN PROGRESS**" and including the details of the licensed Asbestos Removalist Contractor [PCBU].
- When working with products and materials "that may" contain asbestos [ACM] all 'workers' are to wear personal protective equipment [PPE] including coveralls and approved respiratory protection equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices.
- As far as reasonably practicable use non powered hand tools as these generate much less dust [ACD]. Do not use abrasive cutters and sanders on all products and materials "that may" contain asbestos [ACM].
- Wet down or seal the material containing asbestos [ACM] to reduce the release of dust [ACD].
- As far as reasonably practicable work in well ventilated areas.
- Use drop sheets to collect debris containing asbestos [ACM].
- Wet clean or use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 Industrial vacuum cleaners. Household vacuum cleaners must never be used where asbestos is or may be present, even if the unit has a HEPA filter.
- Dispose of smaller products and materials "that may" contain asbestos pieces and collected dust in plastic bags which are clearly labelled "asbestos waste".

- Asbestos cement products [ACM] must not be reused.
- Do not abrade, scrub or water blast the surface of products and materials "that may" contain asbestos.

DEMOLITION WORK PLAN

The partial demolition of the residence and the removal, storage, handling and disposal of building materials must be carried out as far as *reasonably practicable* in accordance with the following Regulations;

- Work Health and Safety Act 2011 and Work Health and Safety Regulations 2011
- WorkCover NSW Code of Practice How to manage and control asbestos in the workplace
- Safe Work Australia Code of Practice How to safely remove asbestos
- NSW Work Health and Safety (Hazardous Substances) Regulation 2001
- NSW Work Health and Safety (Asbestos Removal Work) Regulation 2001
- Australian Standard AS2601 [2001] Demolition of Structures
- NSW Protection of the Environment Operations Act [1997]
- NSW Protection of the Environment Operations [Waste] Regulation [2005]
- NSW Office of Environment and Heritage [OEH] Regulations and Guidelines

A Demolition Work Plan must be submitted to the Local Council and / or the Principal Certifying Authority (PCA), not less than five [5] working days **before commencing any demolition works** involving products or materials "that may" contain asbestos [ACM].

A copy of the Demolition Work Plan must be maintained on site and be made readily accessible to the Council Officer or 'workers' upon request.

ASBESTOS [ACM] REMOVAL CONTROL PLAN

Safe Work Method Statement - Removal & Disposal of Materials that may contain Asbestos

Any work involving the demolition, storage and disposal of products or materials "that may" contain asbestos [ACM] must be carried out as far as reasonably practicable to minimise the release of airborne asbestos dust and fibres [ACD] in accordance with the following requirements;

- Relevant Work Health and Safety legislation including but not limited to WorkCover NSW Code of Practice How to manage and control asbestos in the workplace; Safe Work
 Australia Code of Practice How to safely remove asbestos and NSW Office of Environment
 and Heritage [OEH] requirements.
- The person with Management Control of the workplace and the licensed Asbestos Removalist must, so far as reasonably practicable, and before commencing the asbestos [ACM] removal work, consult with and inform the following people about the asbestos [ACM] removal work and when the work will commence, so as to eliminate or minimise the exposure of the risks associated with asbestos:
 - The person who commissioned the asbestos removal work [Site Management]
 - A person conducting a business or undertaking at the workplace [Contractors]

- The occupants of the domestic premises [Owner or Tenant]
- Anyone occupying premises in the immediate vicinity of the workplace [Neighbours]
- All work procedures are to be devised as far as reasonably practicable to minimise the release of dust and fibres [ACD].
- Appropriate warning signage and barricades are to be erected to prevent as far as reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- The sign must be clearly displayed in a prominent visible position at the front of the site; containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" and including the details of the licensed Asbestos Removal Contractor [PCBU].
- When working with products and materials "that may" contain asbestos [ACM] all 'workers' are to wear personal protective equipment [PPE] including coveralls and approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices.
- As far as *is reasonably practicable*, use non powered hand tools for the removal of the materials *that may* contain asbestos [ACM] as these generate much less dust [ACD]. **Do not use** abrasive cutters and sanders, scrub or water blast the surface of products and materials "that may" contain asbestos [ACM].
- All products and materials "that may" contain asbestos [ACM] are to be kept damp to minimise
 as far as is reasonably practicable the generation of airborne asbestos dust and fibres [ACD].
 Prevent and or contain excess run off water.
- Where reasonably practicable work in well ventilated areas.
- Use drop sheets to collect debris of materials that may contain asbestos [ACM]. Dispose of smaller products and materials "that may" contain asbestos [ACM] pieces and collected dust [ACD] in recommended heavy duty plastic bags which are clearly labelled "asbestos waste".
- Wet clean or use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69 Industrial vacuum cleaners. Household vacuum cleaners must never be used where asbestos [ACM] or [ACD] is or may be present, even if the unit has a HEPA filter.
- Wall cladding and ceiling lining sheets "that may" contain asbestos [ACM] are not to be reused.
- All products and materials "that may" contain asbestos [ACM] or [ACD] are to be stored, transported and disposed of in accordance with the NSW Protection of the Environment Operations Act [1997] and NSW Protection of the Environment Operations [Waste] Regulation [2005]
- All products and materials "that may" contain asbestos [ACM] or [ACD] is to be either wrapped
 in recommended heavy duty plastic sheeting or placed in leak proof lined bins or vehicles and
 appropriately covered and sealed.
- All products and materials "that may" contain asbestos [ACM] or [ACD] are to be stored in a secure area and removed from site as soon as reasonably practicable in a covered leak proof vehicle.
- A Clearance Certificate of Statement, prepared by a suitably competent person i.e. an Occupational Hygienist, WorkCover NSW licensed Asbestos Removalist, licensed Asbestos

Assessor or a "competent person" must be provided to Council upon completion of the works prior to an Occupation Certificate being issued, which confirms that the material "that may" contain asbestos [ACM] or [ACD] has been removed appropriately and the relevant Conditions of Consent have been satisfied.

 All products and materials "that may" contain asbestos [ACM] or [ACD] are to be disposed of as soon as reasonably practicable, at a licensed asbestos disposal site and in a manner approved by WorkCover NSW, NSW Office of Environment and Heritage [OEH]

Safe Work Method Statement - Removal and Disposal of Ceiling Dust that may contain Lead

All Contractors [PCBU] and 'workers' involved in the cleaning, repairing or replacement of ceilings are to follow the following procedures in order to minimise as far as reasonably practicable, health risks from the ceiling dust. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as reasonably practicable entry of anyone not connected with the removal activity into the work area.
- When working with in ceiling voids containing ceiling dust all 'workers' are to wear personal protective equipment [PPE] including coveralls and approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used
- Ceiling voids are to be cleaned of accumulated dust before commencing any work involving partial or complete removal of the ceiling sheets.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as far as is *reasonably practicable*.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of ceiling dust "that may" contain lead to prevent as far as reasonably practicable, dust entering the retained living areas.
- Use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69
 Industrial vacuum cleaners, to prevent the release of dust that may contain lead while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of the collected dust in approved plastic bags which are clearly labelled.
- All ceiling dust containing lead or other contaminants is to be disposed of as far as reasonably practicable in a manner, and at as site, approved by the WorkCover NSW, NSW Office of Environment and Heritage [OEH], appropriate disposal Authority To minimise as far as is reasonably practicable contamination of living areas of the residence, airless spraying of PVA to seal the cleaned surfaces is recommended whenever the ceiling is removed.