

SAC		Air Conditioning Compressor
DP		Downpipe
EF		Exhaust Fan
HL		Heater/Light
HWU		Hot Water Unit - To be removed
MH		Manhole
MB		Meter Box - Electrical
RA		Return Air Grill
		Smoke Detector - Existing
ST		Solar Tube
T		Tap - Garden
WL		Wall Light
		Smoke Detector - New
FL		Fascia Light
S		Sensor
AC		Air Conditioning Duct
RV		Roof Ventilator Existing - To be removed
EL		Eave Light

**PROTECT PROBABLE  
ASBESTOS CEMENT  
[ACM] IN RETAINED  
GABLE ENDS FROM  
DAMAGE DURING THE  
COURSE OF THE  
WORKS**

**PROTECT PROBABLE  
ASBESTOS [ACM] TO  
BACKING BOARD OF  
ELECTRICAL METER  
BOARD DURING THE  
COURSE OF THE  
WORKS**

**REMOVE & DISPOSE  
OF PROBABLE  
ASBESTOS CEMENT  
[ACM] IN EAVE &  
PORCH SOFFITS IN A  
MANNER APPROVED  
BY SAFE WORK NSW,  
NSW OEH & THE HILLS  
SHIRE COUNCIL**

**REMOVE & DISPOSE  
OF PROBABLE  
ASBESTOS CEMENT  
[ACM] IN GABLE END  
IN A MANNER  
APPROVED BY SAFE  
WORK NSW, NSW OEH  
& THE HILLS SHIRE  
COUNCIL**

Note: Cement render & paint  
existing home

**REMOVE & DISPOSE  
OF PROBABLE  
ASBESTOS CEMENT  
[ACM] IN EAVE SOFFITS  
IN A MANNER  
APPROVED BY SAFE  
WORK NSW, NSW OEH  
& THE HILLS SHIRE  
COUNCIL**

**PROTECT POSSIBLE  
ASBESTOS CEMENT  
[ACM] IN RETAINED  
BATHROOM WALLS  
FROM DAMAGE  
DURING THE COURSE  
OF THE WORKS**

**LOOSE-FILL [ACM] AND  
SYNTHETIC MINERAL  
FIBRE [SMF] BATT  
INSULATION OVERALL  
THE ROOF SPACE TO  
BE RETAINED AS PART  
OF THE CONTRACT  
WORKS**

