## Fresh Start

## Work Method Statement

Activity / Task: Polystyrene Wall Cladding Installation Project / Location: All Jobs

Company: Fresh Start

Signed: Chris Moerman Date: 25/07/2016

Principle Contractor: Cape Cod

Accepted by: Fudge Jordan Date: 25/07/2016

version 1.10

Steps	Potential Hazards	Controls / Responsible Person(s)
1. Access to site	<ul> <li>Slips, trips, falls and accessibility.</li> <li>UV light / weather exposure.</li> </ul>	<ul> <li>Site specific induction. By: Fresh Start</li> <li>All "workers" to register before entering the site; to read the General Construction Safety Plan signage; and to read the Site Specific Risk Assessment form. By: Fresh Start</li> <li>Tool box talk to highlight any WHS concerns relative to the site. By: Fresh Start</li> <li>Ensure that the site and work place access is unobstructed. By: Fresh Start</li> <li>Ensure all weather access to work areas. By: Fresh Start</li> <li>Provision of designated waste areas. By: Principle Contractor</li> <li>Storage of materials in designated areas. By: Fresh Start &amp; Fresh Start</li> <li>Provide and maintain barricades to all materials stored on footpath and on site. By: Fresh Start</li> <li>Regular site clean ups. By: Principle Contractor</li> </ul>
<ol> <li>Unloading plant, equipment and tools</li> </ol>	<ul> <li>Manual task injuries</li> <li>Slips, trips and falls.</li> <li>Proximity of other "workers".</li> <li>Public access.</li> </ul>	<ul> <li>Team lifting and carrying. By: Fresh Start</li> <li>Training of "workers" in correct lifting methods. By: Fresh Start</li> <li>Unload and move equipment to designated area to keep footpath / work place access clear. By: Fresh Start</li> </ul>
3. Setting up equipment	<ul> <li>Manual task injuries</li> <li>Slips, trips and falls.</li> <li>Proximity of other "workers".</li> <li>Public access.</li> </ul>	·
4. Carrying materials up ramp Installation of panel wall cladding	<ul> <li>Slips, trips, falls and accessibility.</li> <li>UV light / weather exposure.</li> <li>Electrocution.</li> <li>Fall from height.</li> <li>Manual task injuries</li> <li>Exposure to dust.</li> <li>Exposure to noise.</li> <li>Proximity of other "workers".</li> <li>Public access.</li> </ul>	<ul> <li>Assess the site conditions including the weather and conduct a Site Specific Risk Assessment before commencing installation work. By: Fresh Start</li> <li>Identify that the electrical service has been isolated and that 'tiger tails' are in place as protection from overhead wires and points of attachment before commencing installation work. By: Fresh Start</li> <li>Wear appropriated PPE - hat, long sleeves, sun screen, sunglasses and fluids and reduce exposure where possible. By: Fresh Start</li> <li>Ensure that the guard rails to the ramp are in place and that the surface of the ramp is clean before commencing. By: Fresh Start</li> <li>Ensure that scaffolding is safe and erected by a qualified Scaffolder before commencing. By: Fresh Start</li> <li>Ensure that the perimeter protection is in place before commencing. [Scaffold as working platform] By: Fresh Start</li> <li>Ensure that the edge protection to the roof surface [roof rail] and level work platforms are in place before commencing work from roof surface. By: Fresh Start</li> <li>Training of "workers" in safe working at heights and safe movement on roof. By: Fresh Start</li> <li>Training of "workers" in correct lifting methods. By: Fresh Start</li> <li>Ensure that correct lifting and carrying techniques are used at all times. By: Fresh Start</li> <li>Team lifting and carrying -limiting weights to manageable sizes. By: Fresh Start</li> <li>Ensure "workers" have safety glasses, noise protection, dust protection [disposable], protective</li> </ul>

• Provide MSDS for hazardous substances - polystyrene. By: Fresh Start

- Provide appropriate containment and disposal of waste polystyrene. By: Fresh Start
- Training of "workers" in the safe handling and use of polystyrene. By: Fresh Start
- Training of "workers" in the safe use of power tools. By: Fresh Start
- Ensure all power tools have working safety guards. By: Fresh Start
- Storage of materials in designated areas. By: Fresh Start
- Maintain a clean and tidy work area. By: Fresh Start

- 5. Site clean up on completion of work
- Manual task injuries
- Exposure to dust
- Exposure to hazardous substances
- Remove any temporary barricades if no longer required By: Principle Contractor
- Place all rubbish / debris in designated waste storage area By: Fresh Start
- Leave site / work area in a clean and tidy condition By:

Person responsible for ensuring compliance with SWMS: Chris Moerman
Person responsible for reviewing SWMS control measures: Chris Moerman

Document Updated: 25/07/2016