SAFE WORK METHOD STATEMENT

Page 1 of 5 v1.13

Company Name:	RJC	Project Name/No:	All Jobs	
Work Activity / Task:	BRICKLAYER	Principal Contractor:	Cape Cod Australia Pty. Ltd.	
Prepared by:	Ralph Catto	Date: 21. 4 . 4		
Signature:	POR	Note: Sign off to be prov	Note: Sign off to be provided at Tool Box talk	

Note: Review of Control Measures - If there are any tasks that may be included by way of variation to the plans or an alternative approach to the set task, it is a requirement to carry out a "Specific Risk Assessment" for the tasks.

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
1	Access to site	 Slips, trips, falls and accessibility. UV light / weather exposure 	 Site specific induction. All "workers" to register before entering the site; to read the General Construction Safety Plan signage; and to read the Site Specific Risk Assessment form. 	Contractor Contractor
			Tool box talk to highlight any WHS concerns relative to the site.	Contractor
			 Ensure that the site and work place access is unobstructed. 	Contractor
			Ensure all weather access to work areas.	Cape Cod
		Provision of designated waste areas.	Cape Cod	
			 Storage of materials in designated areas. 	Contractor
			 Provide and maintain barricades to all materials stored on footpath and on site. 	Cape Cod
			Regular site clean ups.	Cape Cod
2	Unloading plant, equipment and	Manual task injuriesSlips, trips and falls.	 Team lifting and carrying. Training of "workers" in correct 	Contractor
	tools	Proximity of other "workers".	lifting and carrying methods. • Unload and move the equipment	Contractor
		Public access.	to designated area to keep footpath / work place access clear.	Contractor
3	Setting up equipment	Manual task injuriesSlips, trips and falls.	Set up in a clear area and maintain a clear travel path.	Contractor

_			
R	evie	wed	bv:

Gary Klomp

On behalf of Cape Cod

Signature

Construction Manager

Position

23,92014

Date

ltem	Job Step	Potential Hazard	Controls	Responsible Person/s
		Proximity of other "workers".Public access.	 Training of "workers" in setting up of plant and equipment and electrical leads. 	Contractor
			 Ensure that all safety guards provided to plant and equipment are properly maintained and used. 	Contractor
			Ensure that all electrical plant and equipment and electrical leads have current tagging.	Contractor
			Ensure that all electrical plant and equipment are attached to a residual current device [RCD].	Contractor
4	Cutting bricks and preparing mortar	Slips, trips and falls.UV / weather exposure.	Assess the site conditions and conduct a Site Specific Risk Assessment before commencing.	Contractor
		Electrocution. Hazardous substances.	 Ensure that work place access is unobstructed. Establish a "No access area" 	Cape Cod & Contractor
		Exposure to dust.Exposure to noise.	round work areas by barricading to prevent access to the area of work.	Cape Cod
		 Manual task injuries Sprains and strains. Cuts and abrasions. 	Ensure that the electrical mixer and 'wet' saw are attached to an earth leakage protection device.	Contractor
		Proximity of other "workers".Public access.	Wear appropriated PPE - hat, long sleeves, sun screen, sunglasses and fluids and reduce exposure where possible.	Contractor
			 Training of "workers" in setting up and safe use of mixer and brick saw. 	Contractor
			 Use appropriate PPE – safety glasses, footwear, noise / hearing protection, dust protection [disposable], gloves and hard hats. 	Contractor
			 Training of "workers" in correct lifting and carrying methods. 	Contractor
			 Ensure correct lifting and carrying techniques are used at 	Contractor

Rev	iewed	bv:

Gary Klomp
On behalf of Cape Cod

Signature

Construction Manager

Position

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			all times.	
			 Rotate "workers" and vary tasks performed. 	Contractor
			Provide MSDS for hazardous substances – silica, lime, cement and sand.	Cape Cod
			 Training of "workers" in the safe handling and use of lime, cement and sand. 	Contractor
			Storage of materials in designated areas.	Contractor
	15 15		Maintain a clean and tidy work area.	Contractor
			Regular site clean ups.	Cape Cod
5	Bricklaying from scaffold	 Slips, trips, falls and accessibility UV light / weather exposure 	Assess the site conditions including the weather and conduct a Site Specific Risk Assessment before commencing.	Cape Cod
		Fall from height	Ensure that work place access is unobstructed.	Contractor
		 Hazardous substances Falling objects Exposure to dust Exposure to noise 	 Establish a "No access area" below overhead work areas by barricading to prevent access to the area of work. Provide a 	Cape Cod
		 Manual task injuries Sprains and strains Cuts and abrasions Proximity of other "workers". Public access. 	 Identify that the electrical service has been isolated and that 'tiger tails' are in place as protection from overhead wires and points of attachment before commencing. 	Cape Cod
		• Fublic access.	 Ensure that guard rails to the ramp are in place and that the surface of the ramp is clean before commencing. 	Cape Cod & Contractor
			 Ensure that the scaffolding is safe and erected by a qualified Scaffolder before commencing. 	Cape Cod
			 Ensure that perimeter protection is in place [scaffolding and edge protection / working platform / 	Cape Cod

Rev	iew	ed	by:
-----	-----	----	-----

Gary Klomp
On behalf of Cape Cod

Construction Manager
Position

Signature

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			toe boards / brick guards] before commencing.	
			 Training of "workers" in safe working at heights. 	Contractor
			 Training of "workers" in correct lifting and carrying methods. 	Contractor
			 Ensure that correct lifting and carrying techniques are used at all times. 	Contractor
			 Rotate "workers" and vary tasks performed. 	Contractor
			 Provide MSDS for hazardous substances - lime, cement and sand. 	Cape Cod
			 Training of "workers" in the safe handling and use of lime, cement and sand. 	Contractor
			 Use appropriate PPE - safety glasses, footwear, noise / hearing protection, dust protection [disposable], gloves and hard hats. 	Contractor
			 Check access ladder for damage / defects before use. 	Contractor
			 Check that the access ladder is stable and secured top and bottom before use. 	Contractor
			 Training of "workers" in safe use of plant and equipment. 	Contractor
			 Ensure that all plant and equipment has working safety guards. 	Contractor
			Use of a brick hoist / elevator to load upper scaffold decks.	Contractor
			 Hoist / elevator to be operated by qualified competent operator ["worker"]. 	Contractor
			 Ensure that a hard hat is worn by hoist / elevator operator ["worker"]. 	Contractor
			Storage of materials in	

Reviewed by:	Gary Klomp	
	On behalf of Cape Cod	

Signature

Construction Manager

Position

SAFE WORK METHOD STATEMENT [cont.]

Page 5 of 5 v1.13

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			 designated areas. Maintain a clean and tidy work area. Regular site clean ups. 	Contractor Contractor Cape Cod
6	Site clean up on completion of work	 Manual task injuries Exposure to dust Exposure to hazardous substances- 	 Remove any temporary barricades if no longer required Place all rubbish / debris in designated waste storage area Leave site / work area in a clean and tidy condition 	Cape Cod Contractor Contractor

Reviewed by:	Gary Klomp	
	On behalf of Cape Cod	
	14	
	Signature	_

Construction Manager
Position

28 9 2014