## **Special Guest**

## Safe Work Method Statement

Project / Location: All Jobs

version 1.1

Activity / Task: Asbestos Removal

Company: Special Guest

Signed by: Test Carpenter Date: 15/03/2017

Principal Contractor: Test Company

Accepted by: Date:

## Potential Hazards Controls / Responsible Person(s) Steps 1. Access to site Slips, trips, falls and Site Specific Induction By: Special Guest accessibility. All "workers" to register before entering the site; to read the General Construction Safety Plan UV light / weather signage; and to read the Site Specific Risk Assessment form. By: Special Guest exposure. Tool box talk to highlight any WHS concerns. By: Special Guest Ensure site access is unobstructed. By: Special Guest Ensure all weather access to work areas. By: Principal Contractor Wear appropriated PPE - hat, long sleeves, sun screen, sunglasses, and fluids and reduce exposure where possible. By: Special Guest Provision of designated waste areas. By: Principal Contractor Storage of materials in designated areas. By: Special Guest Regular site clean ups. By: Principal Contractor Unloading plant Manual task Team lifting and carrying. By: Special Guest and equipment injuries. Training of "workers" in correct lifting methods. By: Special Guest Slips, trips and falls. Unload and move the equipment to designated area to keep footpath / work place access clear. Proximity of other By: Special Guest "workers" and public. Public access. Setting up Manual task Set up in a clear area and maintain a clear travel path. By: Special Guest equipment iniuries. Training of "workers" in setting up of electrical leads, power tools and nail guns. By: Special Guest Slips, trips and falls. Ensure proper use of all safety guards provided to plant and equipment. By: Special Guest Proximity of other Ensure all electrical leads, plant and equipment have current tagging. By: Special Guest "workers" and Ensure electrical equipment is attached to a residual current device [RCD]. By: Special Guest public. Public access. Assess site conditions including weather and conduct a Site Specific Risk Assessment before Removing Slips, trips, falls and • asbestos or ACM accessibility commencing. By: Special Guest sheet from Fall from height Identify the location of the electrical service and that the electrical service has been isolated or ground level safely relocated before commencing work. By: Special Guest Hazardous Provide "Restricted Access" warning signage and establish a "No access area" by barricading to materials prevent access of anyone not connected with the removal activity into the work area and to Exposure to dust control contamination. By: Special Guest Identification of Position warning signage containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" in a services prominent visible position at the front of the site. Signage to include the details of the licensed Electrocution Contractor [PCBU]. By: Principal Contractor Exposure to noise Seal all windows and doors to prevent dust entering the building during the removal and clean up Manual task injuries process. By: Special Guest Cuts and abrasions All products and materials "that may" contain asbestos [ACM] or [ACD] are to be stored, Proximity of other transported and disposed of in accordance with the NSW Protection of the Environment "workers" and Operations Act [1997] and NSW Protection of the Environment Operations [Waste] Regulation public. [2005] By: Special Guest Public access. Prior to the removal process all products and materials "that may" contain asbestos [ACM] or [ACD]

Special Guest

to be sealed with PVA sealant or kept damp. Prevent and or contain excess run off water. By:

- All products and materials "that may" contain asbestos [ACM] or [ACD] is to be either wrapped in recommended 200-micron thick plastic sheeting or placed in leak proof lined bins or vehicles and covered. By: Special Guest
- All products and materials "that may" contain asbestos [ACM] or [ACD] is to be stored in a secure area and removed from site as soon as practical in a covered leak proof vehicle. By:
- All products and materials "that may" contain asbestos [ACM] or [ACD] is to be disposed of in a
  manner, and at a site approved by the NSW Office of Environment and Heritage [OEH], appropriate
  disposal Authority or Local Council. By:
- Care in removing wall sheets and eave soffits to minimise breakage of sheets where possible keep sheets intact. By: Special Guest
- Ensure that adequate lighting and ventilation is available. By: Special Guest
- Systematic safe removal of materials. By: Special Guest
- Training of "workers" in safe working from step and extension ladders. By: Special Guest
- Training of "workers" in the safe removal and handling of products and materials "that may" contain asbestos [ACM] or [ACD]. By: Special Guest
- Ensure "workers" wear safety glasses, noise protection, respiratory protection [disposable], protective footwear, disposable coveralls and gloves during the removal and clean up process. By: Special Guest
- Regularly monitor for air borne dust when removal work is being undertaken. By: Special Guest
- Pick up visible asbestos debris around the removal area, then decontaminate using wet methods or suitable vacuum cleaner. By: Special Guest
- Use approved vacuum cleaning equipment [HEPA] that complies with AS/NZS 60335.2.69 –
  Industrial vacuum cleaners or its equivalent for particulates hazardous to health, to prevent the
  release of lead containing dust while it is being removed. Do not use household vacuum cleaners.
   By: Principal Contractor
- PVA seal residues of asbestos cement that cannot be removed from timber framed members. By:
   Special Guest
- Plastic sheets used for drop sheets and debris is not be reused and is to be disposed of as asbestos waste. By:
- Training of "workers" in correct lifting and carrying methods. By: Special Guest
- Ensure that the correct lifting and carrying techniques are used at all times. By: Special Guest
- Rotate "workers" and vary tasks performed. By: Special Guest
- Ensure running water is available By: Principal Contractor

- Stripping of asbestos or ACM sheet roof covering
- Slips, trips, falls and 
   accessibility.
- UV light / weather exposure.
- Fall from height.
- Hazardous materials.
- Identification of services.
- Flectrocution.
- Falling objects.
- Exposure to dust.
- Exposure to noise.
- Manual task injuries
- Sprains and strains.
- Cuts and abrasions.
- Proximity of other "workers".
- Public access.

- Assess the site conditions including the weather and conduct a Site Specific Risk Assessment before commencing. By: Principal Contractor
- Provide "Demolition in Progress" and "Restricted Access" warning signage and establish a "No
  access area" by barricading to prevent access of anyone not connected with the removal activity
  into the work area and to control contamination. Provide a spotter where necessary. By: Principal
  Contractor
- Position warning signage containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" in a
  prominent visible position at the front of the site. Signage is to include the details of the licensed
  Contractor [PCBU]. By: Principal Contractor
- Identify that the electrical service has been isolated and that 'tiger tails' are in place as protection from overhead wires and points of attachment before commencing. By: Principal Contractor
- Use Licensed Electrician to isolate, disconnect and relate existing services. By: Principal Contractor
- Ensure that the guard rails to the ramp are in place and that the surface of the ramp is clean before commencing. By: Special Guest
- Ensure that the perimeter protection is in place [scaffolding and edge protection] are in place before accessing work from roof surface. By:
- Ensure that the edge protection to the roof surface [roof rail] is in place before accessing the roof surface. By: Special Guest
- Training of "workers" in safe working at heights and safe movement on scaffolding and on roof. By:
   Special Guest
- Training of "workers" in the safe removal and handling of products and materials "that may" contain asbestos. By: Special Guest
- Ensure that the scaffolding is safe and erected by a qualified Scaffolder. By:
- Check the access ladder for damage / defects before use. By: Special Guest
- Check that the ladder is stable and secured top and bottom before use. By: Special Guest
- Correct use of access ladder. By: Special Guest
- Limit use of ladders as working platforms. By: Special Guest
- Ensure "workers" wear hats, safety glasses, noise protection, respiratory protection [disposable], protective footwear, disposable coveralls and gloves during the removal and clean up process. By:
   Special Guest
- Systematic safe removal of materials. By: Special Guest

- Training of "workers" in correct lifting and carrying methods. By: Special Guest
- Team lifting and carrying. By: Special Guest
- Rotate "workers" and vary tasks performed. By: Special Guest
- Ensure that materials are not stored on roof or scaffold. By: Special Guest
- Prior to the removal process asbestos seal the roofing sheets with PVA sealant or wet down. By: Special Guest
- Ensure dampening of the roofing sheets is done well before removal to allow the roof surface to dry sufficiently so "workers" do not slip. By: Special Guest
- Prevent and or contain excess run off water from the roof surface. By: Special Guest
- Remove fixings and remove the asbestos cement sheets with minimal breakage. Lower whole sheets to the ground where possible and place in prepared designated waste area. Provide a spotter where necessary. By: Special Guest
- Regularly monitor for air borne dust when removal work is being undertaken. By: Special Guest
- Provide shade cloth around work area and wet down dust as required to prevent wind borne dust. By: Principal Contractor
- Pick up visible asbestos debris in the roof space and around the removal area and then decontaminate using wet methods or suitable vacuum cleaner. By: Special Guest
- PVA seal residues of asbestos cement that cannot be removed from timber framed members. By: Special Guest
- Plastic sheets used for drop sheets and debris is not be reused and is to be disposed of as asbestos waste. By: Special Guest
- Regular site clean ups. By: Principal Contractor
- Ensure running water is available. By: Principal Contractor

- 6. Site clean up on completion of work
- Exposure to dust
- Exposure to hazardous substances
- Manual task injuries Remove any temporary barricades if no longer required By: Special Guest
  - Place all rubbish / debris in designated waste storage area By: Special Guest
  - Leave site / work area in a clean and tidy condition By: Special Guest

Person responsible for ensuring compliance with SWMS: Test Person responsible for reviewing SWMS control measures:

Document Updated: 15/03/2017