SAFE WORK METHOD STATEMENT

Page 1 of 5 v1.13

Company Name:	TC Building Removal	Project Name/No:	All Jobs
Work Activity / Task:	HOUSE CLEANER	Principal Contractor:	Cape Cod Australia Pty. Ltd.
Prepared by:	Todd Catto	Date: 20.4.15	
Signature:	1 Cutto	Note: Sign off to be provided at Tool Box talk	

Note: Review of Control Measures - If there are any tasks that may be included by way of variation to the plans or an alternative approach to the set task, it is a requirement to carry out a "Specific Risk Assessment" for the tasks.

ltem	Job Step	Potential Hazard	Controls	Responsible Person/s
1	Access to site	 Slips, trips, falls and accessibility UV light / weather exposure. 	 Site specific induction. All "workers" to register before entering the site; to read the General Construction Safety Plan signage; and to read the Site Specific Risk Assessment form. 	Contractor
			 Tool box talk to highlight any WHS concerns relative to the site. Ensure that the site and work place access is unobstructed. 	Contractor
			Ensure all weather access to work areas.	Cape Cod
		Provision of designated waste areas.	Cape Cod	
			Storage of materials in designated areas.	Contractor
2	Unloading equipment and materials	Manual task injuriesSlips, trips and falls.Proximity of other	Unload and move the equipment to designated area to keep footpath / work place access	Contractor
		"workers". • Public access.	clear.Team lifting and carrying.	Contractor
			Training of "workers" in correct lifting and carrying methods.	Contractor
3	Setting up equipment	 Manual task injuries Slips, trips and falls. Proximity of other "workers". Public access. 	 Training of "workers" in setting up equipment. Ensure the proper use of all safety guards provided to equipment. 	Contractor Contractor

Reviewed by:

Gary Klomp

On behalf of Cape Cod

Position

Construction Manager

Date

Page 2 of 5 V1.13

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			Ensure that electrical equipment is attached to a residual current device [RCD].	Contractor
4	Internal Cleaning	 Slips, trips, falls and accessibility Manual task injuries Exposure to dust / fumes. Exposure to noise. 	 Assess the site conditions and conduct a Site Specific Risk Assessment before commencing. Training of "workers" in correct lifting and carrying methods Ensure that correct lifting and 	Contractor Contractor Contractor
		 Hazardous materials. Proximity of other "workers". 	 carrying techniques are used at all times. Rotate "workers" and vary tasks performed. Provide MSDS for hazardous 	Contractor Cape Cod &
		Public access.	 substances – cleaning chemicals. Training of "workers" in the safe handling and use of cleaning chemicals 	Contractor
			Use appropriate PPE – safety glasses, footwear, noise / hearing protection, dust protection [disposable] and gloves.	Contractor
			Ensure "workers" have safety glasses, noise protection, dust protection [disposable], protective footwear.	Contractor
			Check access ladder to upper floor or scaffold for damage / defects before use.	Contractor
			Check that the access ladder is stable and is secured top and bottom before use.	Contractor
		Training of "workers" in the safe use of plant and equipment. Ensure that all plant and	Contractor	
			Ensure that all plant and equipment has working safety guards.	Contractor
			Training of "workers" in safe working and safe movement on site.	Contractor
			Training of "workers" in the safe use of electrical equipment and	Contractor

Day.	: ~	~4	h
Rev	iew	ea	DV:

Gary Klomp

On behalf of Cape Cod

Construction Manager

Position

Signature

Date

Page 3 of 5 V1.13

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			 power tools. Ensure all electrical equipment and tools have working safety guards. 	Contractor
			Maintain a clean and tidy work area.	Contractor
5	External cleaning	 Slips, trips, falls and accessibility UV light / weather exposure. Electrocution 	Assess the site conditions including the weather and conduct a Site Specific Risk Assessment before commencing installation work.	Contractor
The state of the s		 Electrocution Fall from height. Manual task injuries Exposure to dust / fumes. Exposure to noise. 	Identify that the electrical service has been isolated and that 'tiger tails' are in place as protection from overhead wires and points of attachment before commencing.	Cape Cod
W. All Succession (Cont. of the		 Hazardous materials. Proximity of other "workers". 	 Hazardous materials. Proximity of other "workers". Establish a "No access area" below overhead work areas by barricading to prevent access to the area of work. Provide a spotter where necessary. 	Contractor
		Public access.	Ensure that the guard rails to the ramp are in place and that the surface of the ramp is clean before commencing.	Contractor
			Ensure that the scaffolding is safe and erected by a qualified Scaffolder before commencing.	Contractor
TO THE PROPERTY OF THE PROPERT			Ensure that perimeter protection is in place [scaffolding and edge protection / working platform / toe boards] before commencing cleaning of external surfaces.	Contractor
			Ensure that the edge protection to the roof surface [roof rail] and level work platforms are in place before commencing cleaning of windows from roof surface.	Cape Cod & Contractor
			Training of "workers" in safe working at heights.	Contractor
			 Training of "workers" in correct lifting and carrying methods. 	Contractor

Reviewed by: Gary Klomp

On behalf of Cape Cod

Construction Manager

Position

Date

Signature

Page 4 of 5 V1.13

Item	Job Step	Potential Hazard	Controls	Responsible Person/s
			 Ensure that correct lifting and carrying techniques are used at all times. 	Contractor
			 Rotate "workers" and vary tasks performed. 	Contractor
			 Wear appropriated PPE - hat, long sleeves, sun screen, sunglasses and fluids and reduce exposure where possible. 	Contractor
			 Use appropriate PPE – safety glasses, footwear, noise / hearing protection, dust /fume protection [disposable], gloves and hard hats. 	Contractor
			Provide MSDS for hazardous substances – cleaning chemicals.	Contractor
			 Training of "workers" in the safe handling and use of cleaning chemicals 	Contractor
			 Check access ladder for damage / defects before use. 	Contractor
			 Check that the access ladder is stable and is secured top and bottom before use. 	Contractor
THE PERSON NAMED IN COLUMN NAM			 Limit the use of ladders as a work platform. 	Contractor
			 Training of "workers" in safe use of plant and equipment. 	Contractor
			 Ensure that all plant and equipment has working safety guards. 	Contractor
			 Training of "workers" in safe working and safe movement on site. 	Contractor
			 Training of "workers" in correct lifting methods. 	Contractor
			 Ensure that correct lifting and carrying techniques are used at all times. 	Contractor
m postovinski			 Team lifting and carrying - limiting weights to manageable sizes. 	Contractor

Reviewed by: Gary Klo

Gary Klomp
On behalf of Cape Cod

Construction Manager

Position

Signature

Page 5 of 5 V1.13

Job Step	Potential Hazard	Controls	Responsible Person/s
		 Ensure "workers" have safety glasses, noise protection, dust protection [disposable], protective footwear. 	Contractor
	ju S	 Training of "workers" in safe use of power tools and equipment. 	Contractor
		 Ensure all power tools and equipment has working safety guards. 	Contractor
		 Maintain a clean and tidy work area. 	Contractor
Site clean up an	Manual task injuriesExposure to dust	Remove any temporary barricades if no longer required	Contractor
1	• Exposure to hazardous substances-	Place all rubbish / debris in designated waste storage area	Contractor
		Leave site / work area in a clean and tidy condition	Contractor
	Site clean up on completion of work	Manual task injuries Exposure to dust Exposure to	Ensure "workers" have safety glasses, noise protection, dust protection [disposable], protective footwear. Training of "workers" in safe use of power tools and equipment. Ensure all power tools and equipment has working safety guards. Maintain a clean and tidy work area. Manual task injuries Exposure to dust Exposure to dust Exposure to hazardous substances Place all rubbish / debris in designated waste storage area Leave site / work area in a clean

Reviewed by: Gary Klomp
On behalf of Cape Cod

Signature

On benan of cape cou

Date

Position

Construction Manager