

6 Premier Drive, Albion Park NSW 2527
Telephone: 0242574770
Mobile No: 0418 471 343

Email: jonspin@bigpond.com.au

# **HAZARDOUS MATERIALS ASSESSMENT REPORT**

Client: Cape Cod Australia Pty. Limited

Job details: Owner/s: Mr. W. & Mrs. A. Poetscher

Location: 39 Clovelly Road, Randwick NSW

Plans for Job No: 7584/14 Revision No: F Dated: 02-12-14

Council area: RANDWICK CITY

Date of assessment: 17<sup>th</sup> December 2014

Our reference: HM03571214

#### The Client acknowledges that:

This report is provided for **the exclusive information of the Client**. It is a term and condition of the terms upon which this report is provided, that if the Client chooses to rely upon the report, that the Company and the Person making this report will not be liable to the Client or to any other Person who suffers personal or property damage or financial loss in respect of any cause of action or tort, contract or however the cause of action is said to arise

This report is **not a guarantee or warranty** or an all-encompassing report dealing with the above property from every aspect. It is based on the condition of the property and the "**Readily Accessible Areas**" at the time of assessment. It is a reasonable attempt to identify as far as *reasonably practicable*, any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibres [SMF], **visible** at the time of assessment.

This report, based on visual assessment, will not disclose hazardous materials in inaccessible areas, not readily accessible or obstructed at the time of assessment. Areas which are not normally accessible were not assessed and include but are not limited to – inside walls, the interior of a flat roof or beneath a suspended floor filled with earth.

This report is **not a Certificate of Compliance** with the requirements of the WHS Act 2011 and WHS Regulations 2011, relevant Codes of Practice or Australian Standards or NSW Office of Environment and Heritage [OEH] Regulations.



Front southern elevation of the adjoining properties: No.37 & No. 39 Clovelly Road, Randwick

## 1. GENERAL DESCRIPTION OF THE EXISTING RESIDENCE

Estimated age:	Circa 1900 -1910
Type of construction:	Semi detached single storey full brick/ brick cavity construction on a combination of sandstone block footings and brick piers supporting a suspended timber floor system.
External cladding:	Clay masonry brickwork
Roof:	Common traditional cut and pitched hipped and valley structure.  The street elevation section of the roof is terra cotta roofing tiles.  The main roof surface decked with corrugated profile sheet metal roofing.

**Occupancy Status:** Was the residence occupied at the time of assessment?

Yes	✓	No		Not Applicable	
-----	---	----	--	----------------	--

**Orientation:** For the purpose of this report the front of the residence faces:

	Ī	East		West		North		South	✓	Northeast		Northwest		Southeast		Southwest	
--	---	------	--	------	--	-------	--	-------	---	-----------	--	-----------	--	-----------	--	-----------	--

## 2. AREAS ASSESSED

This assessment covers the following "Readily Accessible Areas" of the existing residence layout to identify as far as reasonably practicable any significant hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], ceiling dusts "that may" contain lead, paints "that may" contain lead or synthetic mineral fibre insulation [SMF].

Under Floor Space	✓	Exterior	<b>✓</b>	Roof Surfaces	✓	Roof Cavity	✓	Interior	✓	Carport	✓	
-------------------	---	----------	----------	---------------	---	-------------	---	----------	---	---------	---	--

# 3. ASSESSMENT OF THE EXISTING RESIDENCE LAYOUT FOR HAZARDOUS MATERIALS

Area Assessed	Description and Comment	Assessment / Action
Under Floor Space	Mainly dry sandy loam with some areas of ground water seepage noted.	Appropriate dust suppression measures to be provided.
Note: internal under floor	No evidence of hazardous materials was observed.	No further action is required.
access in Living room	<b>Note:</b> plumbing and drainage work to be performed for new Shower room and Laundry as part of the proposed Contract works.	
Exterior		
Cladding	Clay brick work.  Note: external brick walls to existing Living room, Kitchen, Bathroom and Laundry to be demolished and wall rebuilt as part of the proposed Contract works,	Appropriate dust suppression measures to be provided.  No further action is required.
Eave soffit lining	No eaves to the residence	No action is required.
Roofing	Terra cotta roofing tile s to front street scape roof surfaces.	Appropriate dust suppression measures to be provided.
	<b>Note:</b> tiles to be removed and replaced with pre-finished corrugated profile sheet metal roofing as part of the proposed Contract works	No further action is required.
	Sheet metal roofing to rear roof surfaces  Note: roof structure including skillion roof over Bathroom and Laundry to be removed to accommodate first floor frame as part of the proposed Contract works.	Appropriate dust suppression measures to be provided.  No further action is required.
Front porch	Exposed bull-nosed pre-finished corrugated sheet metal roofing.  Note: not part of the proposed Contract works.	No action is required.
Side Awning	Attached timber framed skillion roof structure with opaque polycarbonate sheet roofing.  Note: structure to be partially removed to accommodate ground floor addition works as part of the proposed Contract works.	Appropriate dust suppression measures to be provided.  No further action is required.
Painting - general	Combination of oil based and acrylic based surface coating to timber windows, fascia and trims.  No exposed lead based paints were observed.	Appropriate dust suppression measures to be provided.  No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Interior		
Entry	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: not part of the proposed Contract works	No action is required.
Hallway	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: new door opening to be formed in common internal brick wall with Bedroom 2 for internal staircase as part of the proposed Contract works	Appropriate dust suppression measures to be provided.  No further action is required.
Bedroom 1 Note 1: fireplace Note 2: Shown as Bedroom 3 on Construction Drawing 3 of 8 for Job No. 7584/14	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: not part of the proposed Contract works.	No action is required.
Bedroom 2 Note 1: roof space access ladder Note 2: Shown as Shower / Laundry / Stairwell on Construction Drawing 3 of 8 for Job No. 7584/14	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: new door opening to be formed in common internal brick wall with Hallway for internal staircase; room to be stripped for Shower / Laundry; existing window to be removed and replaced; ceiling frame to be adjusted and surfaces made good as part of the proposed Contract works.	Appropriate dust suppression measures to be provided.  No further action is required.
Living room Note: fireplace	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: existing external brick wall to be demolished and floor area extended; opening to existing Kitchen to be extended to full height as part of the proposed Contract works.	Appropriate dust suppression measures to be provided.  No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Kitchen / Dining Note: skylight	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: Kitchen to be completely stripped; existing external brick wall to be demolished and re-built; opening to existing living room to be extended to full height; common internal brick walls with Hallway, Laundry and Bathroom to be demolished; skylight to	Appropriate dust suppression measures to be provided.  No further action is required.
	be removed and ceiling replaced as part of the proposed Contract works.	
Hallway	Painted cement render to the walls.  Lath and plaster / fibrous plaster to the ceiling with wide decorative profile plaster cornice and plaster ceiling rose.  Note: existing external brick wall to be	Appropriate dust suppression measures to be provided.  No further action is required.
	demolished and re-built; common internal brick walls with Kitchen, Laundry and Bathroom to be demolished; ceiling replaced as part of the proposed Contract works.	
Laundry	Painted cement render to the walls above wall tiles to 1.5m.	Appropriate dust suppression measures to be provided.
	Fibrous plaster ceiling lining with wide decorative profile plaster cornice.	No further action is required.
	Note: existing external brick wall to be demolished and re-built; common internal brick walls with Hallway and Kitchen, to be demolished; ceiling replaced as part of the proposed Contract works.	
Bathroom Note: skylight	Cement render to the walls under wall tiles from floor to ceiling level.  Fibrous plaster ceiling lining with wide decorative profile plaster cornice.	Appropriate dust suppression measures to be provided.  No further action is required.
	Note: existing external brick wall to be demolished and re-built; common internal brick walls with Hallway and Kitchen, to be demolished; ceiling replaced as part of the proposed Contract works.	
Painting - general	Combination of oil based and acrylic based surface coating to ceilings, walls, doors, windows and trims.  No exposed lead based paints were observed.	Appropriate dust suppression measures to be provided.  No further action is required.

Area Assessed	Description and Comment	Assessment / Action
Pitched Roof Cavity	Traditional cut and pitched timber roof structure and ceiling frame.  Note 1: roof structure to be removed to accommodate first floor frame as part of the proposed Contract works.  Synthetic mineral fibre [SMF] batt insulation noted overall the roof space.  Note 2: Insulation to be retained as part of the proposed Contract works.  Minimal ceiling dust was noted.  Note 3: brick chimneys to Bedroom 1 and Living room to be demolished down to ceiling level as part of the propose3d Contract works.	In our opinion the air quality will not be generally affected during the course of the construction of the new upper floor frame.  Appropriate dust suppression measures to be provided.  No further action is required.
Skillion Roof Cavity	Inspection of the roof cavity was not carried out due to the method of construction.  Note 1: roof structure to be removed and walls built up as required as part of the proposed Contract works.	Appropriate dust suppression measures to be provided.  No further action is required.
Electrical Meter Board	Meter board is located on the common privacy wall to the front porch.  Note: to be retained in current position as part of the proposed Contract works.	No action is required.
Carport	Freestanding timber frame structure with flat roof and pre-finished corrugated profile sheet metal roofing.  Treated pine lattice work enclosing car space.  Note: not associated with the proposed Contract works.	No action is required.
Garden Shed	Freestanding lightweight metal structure on concrete slab.  Note: not associated with the proposed Contract works.	No action is required.
	ea of materials " <i>that may"</i> contain to be removed as part of the proposed	0.0m <sup>2</sup>

## **DEMOLITION WORK PLAN**

The partial demolition of the residence and the removal, storage, handling and disposal of building materials must be carried out as far as *reasonably practicable* in accordance with the following Regulations;

- Work Health and Safety Act 2011 and Work Health and Safety Regulations 2011
- WorkCover NSW Code of Practice How to manage and control asbestos in the workplace

- Safe Work Australia Code of Practice How to safely remove asbestos
- NSW Work Health and Safety (Hazardous Substances) Regulation 2001
- NSW Work Health and Safety (Asbestos Removal Work) Regulation 2001
- Australian Standard AS2601 [2001] Demolition of Structures
- NSW Protection of the Environment Operations Act [1997]
- NSW Protection of the Environment Operations [Waste] Regulation [2005]
- NSW Office of Environment and Heritage [OEH] Regulations and Guidelines

A Demolition Work Plan must be submitted to RANDWICK CITY Council and the Principal Certifying Authority (PCA) if RANDWICK CITY Council is not the PCA, not less than five [5] working days **before commencing any demolition works** involving products or materials "that may" contain asbestos [ACM].

A copy of the Demolition Work Plan must be maintained on site and be made readily accessible to the Council Officer or 'workers' upon request.

#### Safe Work Method Statement - Removal and Disposal of Synthetic Mineral Fibre Insulation

All Contractors [PCBU's] and 'workers' involved in the removal of suspected synthetic mineral fibre [SMF] insulation are to follow the following procedures in order to minimise as far as is reasonably practicable health risks from synthetic mineral fibre [SMF] insulation. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When removing synthetic mineral fibre [SMF] insulation all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as far as is *reasonably practicable*.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of synthetic mineral fibre [SMF] insulation to prevent as far as is reasonably practicable, dust and fibres entering the retained living areas.
- Use approved vacuum cleaning equipment that complies with AS/NZS 603335.2.69 Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust "that may" contain synthetic mineral fibres [SMF] while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of the synthetic mineral fibre [SMF] insulation in sealed approved plastic bags which are clearly labelled.
- All synthetic mineral fibre [SMF] insulation or other contaminants is to be disposed of as far as is reasonably practicable, in a manner, and at a site, approved by WorkCover NSW, NSW Office of Environment and Heritage [OEH], appropriate licensed disposal Authority or RANDWICK CITY Council.

#### Safe Work Method Statement - Lead based Paints

All Contractors [PCBU's] and 'workers' involved in the cleaning, repairing or replacement of suspected lead based paint are to follow the following procedures in order to minimise as far as is reasonably practicable, health risks from lead based paints. These procedures include but are not limited to:

- Appropriate warning signage and barricades are to be erected to prevent as far as is reasonably practicable, entry of anyone not connected with the removal activity into the work area.
- When working with lead based paints all 'workers' are to wear personal protective equipment [PPE] including coveralls and an approved respiratory protective equipment [RPE] in accordance with the requirements of AS/NZS1716 Respiratory Protection devices and AS/NZS1715 Selection, use and maintenance of respiratory protective devices. Eye protection, complying with AS/NZS1336 and AS/NZS1337 whenever full face respirators are not used.
- The property Owner [Client] is to be advised to clear or cover personal effects in adjoining living spaces as much as is practical.
- Any openings between living areas are to be sealed prior to the commencement of any removal work of lead based paints to prevent as far as is reasonably practicable, dust entering the retained living areas.
- Use approved vacuum cleaning equipment [HEPA] which complies with AS/NZS 603335.2.69
   Industrial vacuum cleaners, to prevent as far as is reasonably practicable, the release of dust that may contain lead while it is being removed. Do not use household vacuum cleaners even if the unit has a HEPA filter.
- Dispose of collected lead based paint dust in sealed approved plastic bags which are clearly labelled.
- All dust containing lead or other contaminants is to be disposed of as far as reasonably practicable in a manner, and at a site, approved by WorkCover NSW, NSW Office of Environment and Heritage [OEH], appropriate disposal Authority or RANDWICK CITY Council.

#### 4. AREAS NOT ASSESSED

With the exception of the skillion roof section all other areas associated with the proposed building works were able to be assessed.

#### 5. UNDETECTED HAZARDOUS MATERIALS

Due to the level of accessibility including the presence of obstructions the overall degree of risk of **undetected** hazardous materials is considered as far as *reasonably practicable* to be:

Low ✓ Moderate Moderate to High High	
--------------------------------------	--

## **CERTIFICATION**

This document certifies that the existing residence layout described in this report has been assessed as far as *reasonably practicable* for the inclusion of hazardous materials i.e. materials "that may" contain asbestos [ACM] or [ACD], paints "that may" contain lead or synthetic mineral fibres [SMF] in the existing structure.

This assessment and report was carried out by: John Spindler

**Builders Licence No. 84050C** 

Signed for and on behalf of JONSPIN Building Services Pty. Limited

John Spindler

Date of Issue:17th December 2014